G R S IX 5]

Previous references

File No 112-17

Serial Nos 1—4

Later references

GENERAL AND REVENUE SECRETARIAT

Serial Nos 1—4

Part B for May 1918

SUBJECT

Administration Report for 1916-17 of the City Improvement Trust Board, Mysore

Sl 4 order no 6490-500 dt 24 J-18

Recorded the above To,
The Chairman City I.T. Board
Chief Engineer & Ex-officio Sanitary Commr
Mess
" Press

G. R. S III—1[illegible]

1917-S

GENERAL AND REVENUE SECRETARIAT

(Ml)

NOTES

File No. 112-17

FILE HEADING

Administration Report of the Mysore City Improvement Trust Board

From

The Comptroller, Mysore Govt

No 5540 / WAD I 388 Dated 11th Oct 1917 Received 16th Oct 1917

Diary No 1012	Enclos 2 Spare Copies	Serial No 1

BRIEF ABSTRACT OF LETTER

Submits the preliminary accounts for 1916-17

* NOTES AND ORDERS

From the Chairman, City Improvement Trust Board Mysore

No 327-S 54 / C 130 of 16-17 dt 25.10.17.

Submits the admn Report for 1916-17 together with the statistical statements

received only 2 copies were required

1 Draft never sent

Rev Secy

16/3/18

NOTES—First Sheet

WD 1282—GPB—20 000—16-11 16

G R S III [redacted]

General a[redacted] R[redacted]
Secret[redacted]

Mr File No. 112 of 1917

Serial No	
3	From the Comptroller, Mysore Govt No W a 2I 1320 & 15th/16th March 1918 Submits the final accounts of the Trust Bd for the year 1916–17 A draft forwarding 1 set of the statements for being printed and kept ready for issue along with the Govt Review is subd.
	Issue MK 23/3
4	To the Superintendent, Govt Press, Bangalore No 5313 & 23 3 1918 Forwards for being printed 1 set of the Report ~~work~~ and the statements
	3rd revised draft news as directed by the Revsr is submitted MK 26/3/18
	Revsr)
5160 26/3/18	Dewan) 4 DZ 26 3 18 5 Typed draft approved by the Dewan 1-5-18
	6 To be remtd to Dewan with a S.S N. DZ 1 5 18

Mom—Contn sheet

STATEMENT OF CASES SUBMITTED FOR THE ORDERS OF HIS HIGHNESS THE MAHARAJA DURING THE TOUR OUTSIDE THE STATE IN May 1918

Serial No	Subject	Recommendation of Council or Member of Government in charge as the case may be	Dewan's recommendation	Orders of His Highness	Orders regarding submission of file (*vide* foot note)
7796 C	Draft review on the report of the working of the Board of Trustees for the improvement of the City of Mysore for the year 1916-17.	May be approved	May be approved. 4 5 18 Dw	1277 approved by His Highness Private Secretary 10 5.18 Secretary Dewan 12 5.18 IV Dewan copy	C

NOTE.—The letter a b or c may kindly be inserted by the Private Secretary to His Highness in the last column to indicate whether—

File may be submitted at once — a
File may be submitted after His Highness' return — b
File may not be submitted at all — c

WD 2105—GPB—300—16-2-16

5

Record of Cases submitted for the Orders of His Highness the Maharaja

Subject.

4 Draft review of the report on the working of the Board of Trustees for the improvement of the city of Mysore for the year 1916-17

Order

Submitted to His Highness

I submit herewith a draft review on the report of the working of the Board of Trustees for the improvement of the City of Mysore for the year 1916-17, for His Highness' gracious approval.

M. Visvesvaraya

4th May 1918

It is requested that in future communications on the subject, the No and date of this letter and the distinguishing letters below the number as given opposite may be quoted and addressed to the Comptroller Mysore Government

In the communications Jud 112-17-7

No 5500 Fin I 388 17-2 OFFICE OF THE COMPTROLLER, MYSORE GOVERNMENT,

FORM *Dated Bangalore, the* 11th October 1917

~~DIWAN BAHADUR J. S. CHAKRAVARTI, Esq., M.A.,~~

M. N. Krishna Rao Esq., ~~F.R.A.S., ETC.,~~

Comptroller to the Government of
His Highness the Maharaja of Mysore

To

B. Ramaswamaiyya, Esq, B.A., B.L.,

Secretary to the Government of Mysore,

Revenue *Department*

SIR,

As required by Section 33 of the Mysore City Improvement Regulation No. III of 1903, I have the honor to forward herewith the preliminary accounts of the Mysore City Improvement Trust Board for the year 1916-17 together with a statement showing the details of Expenditure under Service Heads.

I have the honor to be,

Sir,

Your most obedient servant,

SAM.

Assistant Comptroller.

Accounts of the myson City Improvement

Receipts.	amount			Total		
Grant from Government				4,25,182	0	0
Rent from Buildings	332	9	4			
Sale of Model Houses	478	7	8			
Sale of Value of Model Houses	77	7	6			
Sale proceeds of Old Materials	8,869	0	0			
Sale of land	7,513	11	1			
Interest on Sale of Land	10	4	0			
Sale of Experimental Houses	477	9	3			
Interest on Sale of Experimental Houses	38	4	8			
Sale of Trust Houses	293	3	3			
Repayment of Loan	13,264	1	5			
Interest on Repayment of Loan	1,441	6	6			
Fines, refunds and Miscellaneous cash receipts	3,245	15	4			
Contribution towards Municipal Office Building	5,000	0	0	41,042	0	0
Net receipts under Suspense Heads	1			@ 48 936	10	2
Net amount of Deposit transactions for 1913-14 debited in accounts now adjusted				1,949	9	7
Total receipts				5 17,110	3	9
Opening Balance				4,721	11	2
GRAND TOTAL Rs				5 21 831	15	0

@ SUSPENSE HEAD FIGURES

Receipts			
Advance	8262	12	8
Suspense			
Expenditure			
Advance	6,164	9	2
Suspence			
Difference	2,098	3	6
Balance of deposits as per Trust Board accounts for Munelf credited to Fire Headrow adjustment	18 838	6	8
	8 936	10	2

Trust Board for the year 1916-17 (Final)

FR THE SERVICE
OARD

Expenditure	Amount			To		
ESTABLISHMENT -						
I Direction	29,083	9	1			
II Construction	5 838	6	4			
Refunds	866	2	7	31,055	12	10
MISCELLANEOUS PUBLIC IMPROVEMENTS						
a) Drainage and other works	3,44,767	3	8			
b) Buildings	33,298	9	8			
c) House Building Loans	39 999	2	2			
d) Tools and Plant	332	15	5			
e) Refunds and Law charges	309	10	4			
f) Survey works	226	6	1			
g) Printing charges	31	4	0	4,18,965	3	
Total Expenditure				4,50,021	0	2
CLOSING BALANCE				71,810	14	10
GRAND TOTAL				5,21,831	15	0

Assistant Comptroller

15-3-18 RS

SHOWING THE DETAILS OF EXPENDITURE UNDER THE SERVICE HEADS OF THE MYSORE CITY IMPROVEMENT TRUST BOARD FOR THE YEAR 1916-1917

Particulars	amount	total
I DIRECTION -		
1 Pay and allowance of Chairman	10,775 0 0	
2 " Establishment	17,607 15 11	
3 Travelling allowances	96 12 0	
4 Contingencies	769 14 7	
5 Recovery of excess Permanent Travelling allowances drawn by Mr S Aswathanarayana Rao	-425 12 04	
6 Contribution paid to Mysore city Municipality	259 10 11	29,083 9 1
II CONSTRUCTION -		
A 1 Pay and allowances of Assistant Engineer	3,627 11 2	
2 " Establishment	1,064 0 0	
3 Travelling allowances	60 6 0	
	4,752 1 2	
B 1 Pay and allowance of Sub-Assistant Engineer		
2 " Establishment	1,086 5 2	
3 Travelling allowances		
4 Contingencies		
	1,086 5 2	
Total of A and B		5,838 6 4
Refunds		-3,866 2 7
TOTAL OF I & II		31,055 12 10
III MISCELLANEOUS PUBLIC IMPROVEMENTS -		
Forming foot paths on the Sayaji road from the Curzon Park North gate up to Memorial fountain in the Mysore city	526 4 0	
Paving the bed of the storm water drain near the Hardinge circle up to the Pleasure Palace road culvert in Mysore	9,400 14 10	
Constructing 3 Octri Ockad buildings at the three entrance gates viz Seringapatam road entrance, Nanjangud road entrance and Melkote road to the Mysore city	1,272 4 0	
	11 199 6 10	

B.F 11 199-6-40

Acquisition of properties in	Lashkar Mohalla	5,474	12	2
"	Devaraj Mohalla	10,758	15	11
	Krishnaraj Mohalla	12,513	2	3
"	Nazarabad Mohalla	2,274	1	5
"	No IV Drainage area composing of block No 78,79, and 69 B	8,182	1	6
Construction of the Municipal Office building in the Mysore city		5,031	0	0
Laying pipe sewers in No III Drainage area part 2		3,288	14	5
Filling the western portion of Northern arm of Doddakere		7,279	14	1
Construction of outfalls sewer works		415	11	9
Laying out sewage farm with distributary channels at the end of outfall sewer		6,329	11	10
Laying pipe sewers in No IV drainage area		-1,391	3	3
Laying out Bakshi Bassapaji Urs garden extension		19	1	0
Laying pipe sewers in No V drainage area		10,338	2	10
Improving Doddakere tank bund road		872	3	0
Improving Karanji Tank bund road		1,713	3	2
House Building Loans		39,999	2	2
Refunds and Law charges		309	10	4
Survey works		226	6	1
Improving the junction to the north of town hall at Mysore		4,663	8	0
Improvement of Devaraj Market		30,462	6	11
Construction of Model Houses		-4,237	7	4
Covering a portion of Doddakere feeder channel on Chamaraj road		1,330	7	0
Tools and Plant		332	15	5
Forming a new triangle with curb stones near the Cowkaruhalli along the Chamaraj road		651	15	6
Putting up curb stones on either side of the road newly opened to the south of the masonic lodge in the Curzon Park Mysore city		2,704	12	0
Running separate incandescent and street lighting circuits on the right side of the Krishnaraj and Vani Vilas road and deviating the existing lines from the centre of the respective roads and fixing the lamps near the foot-path	Krishnaraj Road	2,939	0	0
	Vani Vilas Road	1,872	0	0
Improving the Jeevanna Rao tank bed		3,417	12	0

4

Filling and improving the fort rampart wall at the Krangere entrance to the Mysore city	552	13	0
Maintenance and repairs during the year 1916-17 of the drainage works completed by the Board of Trustees	3,438	1	4
Levelling undulations in the Krangere, Mysore city the cost being met from the savings in the estimate of Rs 3,000/- for repairing and improving the fort rampart wall at the Krangere entrance to the city			
Laying out a complete pipe sewage system in No V drainage area of the Mysore city			
Acquisition of properties in Mandy Mohalla	6,433	12	0
Improving the junction of the railway station and Viceroy roads near the entrance to the Railway station compound	2,553	14	3
Widening the foot paths in Sayaji road	4	8	0
Planting Avenues (a part of the cost to be chargeable to the Municipality	3,020	0	1
Laying pipe sewers in Ittigegud drainage area	30,799	15	1
Acquisition of properties in Ittigegud drainage area	1,500	0	0
Laying out Chamundi extention	30,342	6	0
Improving the surroundings of the locality outside the eastern gate of Curzon Park	-20	3	9
Laying pipe sewers in Narsahad drainage area	44,395	4	10
Draining the marsh below Kukkarhalli tank	6,848	8	6
Filling in the large gaps in the masonery parapet walls of the fort at Mysore	1,125	0	0
Improving the junction of the Chamaraja and Doddakere tank bund roads near the Police out post	1,282	12	10
Improving and realighning the foot-path along the Sayaji rao road in front of the new Mothikhana buildings and the proposed Municipal Office building	2,083	8	0
Filling in the eastern fort ditch and deverting the storm water of the fort into Doddakere	2,213	10	0
Eradicating the trees and scrub jungle from the fort wall at Mysore	190	7	1
Laying pipe sewers in No III drainage area Part I	65,962	11	2
Shifting electric poles and reducing the width of Chamaraja road	1,122	5	3
Printing charges	31	4	0
Improvement of storm water drain in No IV Drainage area	27	4	11

5728979-9-7

Frecting a compound wall to the cremation ground in front of the Madhuvana garden at Mysore	260	15	2.	
Constructing under ground drains and diverting the surface water at the Statue Square at Mysore	386	10	6	
Constructing a storm water drain on the old Idga road of Nazababad Mohalla Mysore				
Dismantling the rampart wall on the eastern wall on the Eastern side of the fort rampart wall	1,005	8	6	
Acquisition and demolition of properties in fort and Krishnaraja Mohalla	26,790	9	0	
Removing the health camp sheds on the Srirangapatam road near the Harangere entrance to the Mysore city and reconstructing the same elsewhere	650	6	1	
Constructing circular Parapet walls with ornimental railings at the junction of the Chamaraja and Viceroy roads and Chamaraja and Krishnaraj roads	680	4	0	
Constucting new buildings round the Deveraj market Square				
Laying pipe sewers in No\ 2 drainage area	6,565	3	6	
Forming roads at the fort south gate	1,010	14	0	
Forming roads in the Wellington Lodge compound	120	0	0	
Fixing curb stones to the new road to the south of gun shed	188	3	0	
Installing lights in Albert Victor road from Harding circle to Statue Square	8,427	0	0	4,18965-3-4

--------\|/--------

14/3/18

D 2272

Please address all future communications to the Comptroller to the Govt of H H the Maharaja of Mysore
In reply to this Comn please refer to
No W.A.D. I. 1320.

OFFICE OF THE COMPTROLLER TO THE GOVERNMENT OF HIS HIGHNESS THE MAHARAJA OF MYSORE

Dated, Bangalore, the 15th March 1917.

FROM

M N KRISHNA RAO, ESQ, B A,

Comptroller to the Government of

His Highness the Maharaja of Mysore

To

D. Ramaswamyaiya, , ESQ, B.A., B.L.,

Secretary to the Government of Mysore,
Revenue *Department*

SIR,

As required by section 33 of the Mysore City Improvement Regulations No. III of 1903, I have the honor to forward herewith the final accounts of the Mysore City Improvement Trust Board for the year 16-17 together with a statement showing the details of expenditure under Service Heads.

I have the honor to be,

Sir,

Your most obedient servant,

Assistant Comptroller.

M1/15-3.

[redacted]

Accounts of the Mysore City Improvement Trust Board for the year 1916-1917 Summary

Receipts	Amount			Total		
Grant from Government				425,182		
Rents from Buildings	332	9	4			
Sale of Model Houses	478	7	8			
Interest on sale of Land	10	4				
Sale proceeds of Old Materials	8,869					
Interest on value of Model Houses	77	7	6			
Fines, Refunds, and Miscellaneous Receipts	3,245	15	4			
Repayment of Loan	13,264	1	5			
Interest on Repayment of Loan	1,441	6	6			
Sale of Land	7,513	11	1			
Sale of Experimental Houses	477	9	3			
Interest on sale of Experimental Houses	38	4	8			
Sale of Trust Houses	293	3	3			
Contribution towards Municipal Office Building	5,000			41,042		
Net Receipts under Suspense Heads				2,098	3	6
Total Receipts				4,68,322	3	6
Opening Balance				4,721	11	3
Grand Total				473043	14	9

Suspense head figures

Receipts –

Advances Rs 8262-12-8

Suspense

Total 8262-12-8

Expenditure –

Advance 6164-9-2

Suspense.

Total 6164-9-2

Difference Rs 2098-3-6

Accounts of the Mysore City Improvement Trust Board for the year 1916-1917 Provisional

No	Receipts	Amount			Total		
1	Grant from Government				425,182		
2	Rents from Buildings	332	9	4			
3	Sale of Model Houses	478	7	8			
4	Interest on sale of Land	10	4				
5	Sale proceeds of Old Materials	8,869	.	.			
6	Interest on value of Model Houses	77	7	6			
7	Fines, Refunds, and Miscellaneous Receipts	3,245	15	4			
8	Repayment of Loan	13 264	1	5			
9	Interest on Repayment of Loan	1,441	6	6			
10	Sale of Land	7,513	11	1			
11	Sale of Experimental Houses	477	9	3			
12	Interest on sale of Experimental Houses	38	4	8			
13	Sale of Trust Houses	293	3	3			
14	Contribution towards Municipal Office Building	5,000			41,042		
	Net Receipts under Suspense Heads				2,098	3	6
	Total Receipts				4,68,322	3	6
	Opening Balance				4,721	11	3
	Grand Total				473043	14	9

Suspense head figures

Receipts -

Advances Rs 8262-12-8

Suspense

Total 8262-12-8.

Expenditure -

Advance 6164-9-2

Suspense.

Total 6164-9-2

Difference Rs 2098-3-6

1916 - 17 Preliminary

Expenditure	Amount			Total		
Establishment –						
I Direction	29249	10	6			
II Construction	5638	6	4			
Refunds	-3866	2	7	31,221	14	3
III Miscellaneous Public Improvements						
(a) Drainage and other works	344,767	5	10			
(b) Buildings	33248	9	9			
(c) House Building Loans	39,999					
(d) Tools and Plant	332	15	5			
(e) Refunds and Law charges	309	10	4			
(f) Survey Works	226	6	1			
(g) Printing Charges	31	4		4,18,965	3	4
Total Expenditure				4,50,187	1	7
Closing Balance				22856	13	2
					0	
Grand Total				47,3043	14	9

Accountant

Accountant

10-10-17

Statement showing the details of expenditure under Loan Scheme
Heads of the Mysore City Improvement Trust Board for the year
1916 – 17

Particulars	Amount			Total		
Establishment Charges —						
I Direction						
1 Pay and allowance of Chairman	10,775					
2 " — " of Establishment	17,607	15	11			
3 Travelling allowances	96	12				
4 Contingencies	769	14	7	29249	10	6
II Constructional						
A 1 Pay and allowance of Asst Engineer	3,627	11	2			
2 " — " Establishment	1,064					
3 Travelling allowance	60	6				
4 Contingencies						
B 1 Pay and allowance of Sub Asst Engineer						
2 " — " Establishment	1086	5	2			
3 Travelling allowances						
4 Contingencies						
Total of A + B 2nd Cop II & III				5838	6	4
				35088		
Refunds				-3866	2	7
Total of Establishment Charges I and II				31,221	14	3
III Miscellaneous Public Improvements						
Forming foot paths on the Sayaji Road from the Curzon Park North gate up to Memorial Fountain in the Mysore City (26)	626	4				
Paving the bed of the storm water drain near the Hardinge Circle up to the Pleasure Palace Road Culvert in Mysore (32)	9400	14	10			
Constructing 3 Extra Metal Buildings at the three entrance gate viz Srirangapatana Road entrance, Nanjangud Road entrance and Hegganadevanakote Road to the Mysore Re (34)	1275	4				
Acquisition of properties in Kashkar Mohalla	5474	12	2			
" Dewan's Mohalla	10,758	15	11			
" Krishnaraj Mohalla	12,513	2	3			
" Nazarbad Mohalla	2274	1	5			
IV Drainage area — Comprising of blocks Nos 78, 79, 69 B	9182	1	6			

9	Construction of the Municipal office building in the Mysore City	(1)	5031		
10	Laying Pipe Sewers in No III Drainage area Part II	(2)	3288	14	
11	Filling in the Western Portion of Northern area of Doddakere	(5)	7279	14	1
12	Construction of Outfalls Sewer Works	(3)	415	11	9
13	Laying out Sewage farm with distributing channels at the end of outfall sewer	(4)	6329	11	10
14	Laying Pipe Sewers in No IV Drainage area	(7)	-1391	3	3
15	Laying out Bakshi Basappaji two Garden Extension		19	1	
16	Laying Pipe Sewers in No V Drainage area	(5)	10,338	2	10
17	Improving Doddakere South Bund Road		872	3	0
18	Improving Karanji South Bund Road	(12)	1713	3	2
19	House Building Loans		39,999	2	2
20	Refunds and Law Charges	(10)	309	10	4
21	Survey Works	(1)	226	6	1
22	Improving the junction to the North of Town Hall at Mysore	(13)	4663	8	
23	Improving of Devaraj Market	(14)	30,462	6	11
24	Construction of model Houses	(15)	-4237	7	4
25	Covering a portion of Doddakere feeder channel on Chamaraj Road		1330	7	
26	Tools and Plant		332	15	6
27	Forming a new Triangle with curb stones near the Cauvery Hall along the Chamaraj Road	(44)	651	15	6
28	Putting up curb stones on either side of the roads newly opened to the south of the masonic Lodge in the Aramane Bank Mysore City		2704	12	
29	Running separate underground and street lighting circuits on the right side of the Krishna Raj and Vani Vilas Road and drawing existing lines from the centre of the respective roads and fixing the Lamps near the foot path	(30)	2937 1972		
30	Improving the Devaraja Raja Tank bed		3417	12	
31	Repairing and improving the fort rampart wall at the Karanjee or entrance to the Mysore City		652	13	
32	Maintenance and repairs during the year 1916-17 of the drainage works completed by the Board Trustees		3438	1	4
33	Levelling undertaken in the Karanji, Mysore City the cost being met from the savings in the estimate of Rs 3000/- for repairing and improving the Fort rampart wall at the Karanjee entrance to the City				

Laying out a complete pipe sewerage system in No V Drainage area of the Mysore City		1,73,962	9	4
Acquisition of Properties in Maandy Mohalla near the junction of the Rly Station and Viceroy Roads near the entrance to the Rly Station Compound	(16)	2553	14	3
Widening the foot paths in Sayaji Road		4	8	
Planting Avenues (a part of the cost to be chargeable to the Municipality	(41)	3020		1
Laying pipe sewers in the Irrigated Drainage area	(17)	30799	15	1
Acquisition of properties in the Irrigated drainage area		1500		
Laying out Chamundi Extension	18	30342	6	
Improving the surroundings of the locality outside the eastern gate of Curzon Park		-20	3	9
Laying pipe sewers in Nazarabad Drainage area	(19)	44395	4	10
Draining the marsh below Kukkarahalli Tank	(20)	6848	8	6
Filling in large gaps in the masonery parapet walls of the Fort at Mysore	(21)	1125		
Improving the junction of the Chamaraja and Doddakere Bank Rund roads near the police out post	(22)	1282	12	10
Improving and realigning the foot path along the Sayaji Rao road in front of the new Mothukarina building and the proposed Municipal office building		2083	8	
Filling in the Eastern Moat deep and diverting the storm water of the Fort into Doddakere	(23)	2088	0	10
Eradicating the trees and scrub jungle from the fort wall at Mysore	(24)	2213	10	
Laying pipe sewers in No III Drainage area Part I	(25)	190	7	
Shifting Electric Poles and reducing the width of Chamaraj Road	(38)	65,962	11	2
Erecting charges		1122	5	3
Improvement of storm water drain in No IV Drainage area	(27)	31	4	
Erecting a compound wall to the cremation ground in front of the Madhuvana garden at Mysore	(43)	27	4	11
Constructing underground drains and diverting the surface water at the statue square at Mysore	(28)	260	15	2
Constructing a storm water drain on the old Daga Road of Nazarbad mohalla Mysore		386	10	6
7 Dismantling the rampart wall on the Eastern wall on the Eastern side of the Fort rampart (2) during the health camp sheds on the Srirangapat Road near the Entrance to the Mysore City and reconstructing the same elsewhere (45) and demolition of properties in Fort and		1005	8	6
		650	6	1
		26790	9	4

40797

60	Constructing circular parapet walls with ornamental railings at the junction of the Chamaraja and Vicroy roads and Chamaraj and Krishna	8	680	4
61	Constructing new buildings round the Devaraja market Square			
62	Laying pipe sewers in No 2 drainage area	(33)	6565	8 6
63	Planning roads at the Fort south gate	(34)	1010	14
	Planning roads in the Willingdon Lodge compound	(35)	126 120	
65	Fixing curb stones to the new roads to the south of gun shed	149	188	3
66	Installing lights in Albert Victor road from Hardinge circle to Statue Square	(39)	8427	
		Total		

15/10/27

Enclosures
1 Board resolution
2 Report
3 13 Statements and one appendix (a) } in triplicate

13

D 1083

Mysore City Improvement Trust Board,
Chairman's Office,
Dated Mysore, the 25th October 1917

No S 27 - S 54/C 13-916-17

Enc Nil 112-17-2

From

T G Lukshmana Rao, Esq., L C E.,
Chairman, City Improvement Trust Board,
Mysore

To

B Ramaswamiah, Esq., B A., B L.,
Secretary to the Government of His Highness
the Maharaja of Mysore, Revenue Department,
Bangalore.

Sir,

I have the honour to forward herewith in triplicate the Report on the working of the Board of Trustees for the Improvement of the City of Mysore for the year 1916-17 with the statistical statements relating thereto.

A copy of the resolution of the Board of Trustees No.X dated the 16th instant adopting the report is also submitted

I have the honour to be
Sir,
Your most obedient servant,

T Lukshmana Rao
Chairman
25/10/17

From

The Chairman,

City Improvement Trust

Board

To

The Secretary to the Govt

the Maharaja of Mysore, ns

Dated Department, Bangalore

Despatched 25th October 1917.

Received

General No. 327 - 5.52/C.130/26-17

No

Enclosure No as

Subject.

Submitting in duplicate Administration Report of the Improvement Board for the year 1916-17 with statistical enclosures

One copy returned to the Board for IV

Only one copy received on 30.10.17

One Copy returned by Mr. D. Subramaniah was subsequently given to me

Dy III 2.11.17

Proceedings of the Fourth Ordinary Meeting of the Board of Trustees for the Improvement of the City of Mysore held at the Chairman's Office (Pangacharlu Memorial Hall) on ~~Monday~~ Tuesday the 16th October 1917 at 8 A.M.

PRESENT

Mr T Lukshmana Rao, L C E , Chairman,

Trustees

Present	Absent
1 Mr G Narayana Rao, B A ,B L ,	1 Mr R.H Campbell, I.C S.,C I E
2 Mr J V Karve, M B ,D P H ,	2 Dr M Srinivasa Rao, M A ,M D ,
3 Mr M Venkatakrishnaiah	3 Mr K C Ranga Iyengar, B A , Rao Bahadur
4. Mr Mahamud Jaffer Sahib	
5 Mr M Anantharajiah	

XXX XXX XXX

1. Report on the working of the Board of Trustees for the Improvement of the City of Mysore, for the year 1916-17

Resolved that the report be adopted and submitted to Government.

XXX XXX XXX

Sd/-T.Lukshmana Rao,

C h a i r m a n

"C o p y"

T Lukshmana Rao

Chairman

C8

ADMINISTRATION REPORT OF THE MYSORE CITY IMPROVEMENT TRUST BOARD FOR THE YEAR 1916-17.

INTRODUCTION .- The year under report is the 14th year of the Board's existence, and the fourth year of the working of the arrangement, under which a whole-time officer is appointed as the Chairman of the Trust Board and the President of the Municipal Council, Mysore

CHAPTER I ADMINISTRATION

Part I. Personnel of the Board and the meetings of its members

CHAIRMAN - Mr T G.Lukshmana Rao, L C E , Executive Engineer continued as Chairman of the Trust Board during the year

2 EX-OFFICIO TRUSTEES - There were no changes among the Ex-Officio Trustees Under Government Notification No.7015-M1.159-16-4 dated the 4th May 1917, however, Dr.L. Srinivasa Rao, M.A ,M.D , D.P H., etc , Sanitary Commissioner was deemed the Deputy Sanitary Commissioner, for the purposes of section 4 of the City of Mysore Improvement Regulation.

3. TRUSTEES APPOINTED BY GOVERNMENT - Mr Mirza Mohammad Ismail, B A , appointed under Government Notification No.4836/M1 11-15-2 dated the 4th January 1916 to act for Mr.P.F Campbell, C I.E , on the Board of Trustees during the latter's absence from Mysore ceased to be a Trustee from 24th September 1916.

4. The term of office of Messrs. M F Campbell, C I E , Mahamud Jaffer Sahib and Rev.C W Dawday as nominated Trustees having expired, the Government in their Notification No 4195/M1 159-16-2 dated the 4th January 1917 appointed ~~Mr.T.Venkate-~~

Mr. M. Venkatakrishniah in the place of Rev. G. W. Sawday, re-appointing the other two gentlemen for a further period of two years as Trustees on the Board of Trustees for the Improvement of the City of Mysore.

5. TRUSTEES ELECTED BY THE MUNICIPAL COUNCIL - The election by the Mysore City Municipal Council of Messrs. M. C. Ranga Iyengar, B A , Rao Bahadur and M. Anantharajiah, two Municipal Councillors as Trustees on the Board was also approved by Government, and notified in the Mysore Gazette in the said Notification.

6. CONSTITUTION OF THE BOARD - Appendix A, shows the names of Trustees constituting the Board of Trustees for the Improvement of the City of Mysore at the close of the year under report

7 BOARD'S MEETINGS - The Trustees of the Board held twelve ordinary meetings during the year under report. An adjourned meeting was held on the 7th May 1917 for the consideration of certain subjects on the agenda for April 1917, that could not for want of time, be discussed on the meeting day of that month. In all, meetings of the Trustees were held on 13 occasions during the year. The dates on which these meetings were held and the number of Trustees that were present at each of them are shown in statement No. 1 appended.

8 WORK OF THE COMMITTEES APPOINTED BY THE BOARD - The Committee appointed under the Board's resolution of 16th January 1914 to suggest definite proposals as to which of the properties notified under the old acquisition estimates were to be withdrawn from acquisition, completed its work by submitting detailed recommendations in the matter The reports of this committee in respect of properties in the Mandi, Krishnaraj and Nazarbad mohallas were finally passed by the Board during

the year under report, those relating to Lakshar and Devaraj mohallas being reserved for approval during the current year.

PART II. IMPROVEMENT SCHEMES

DRAWN UP AND ESTIMATES PASSED BY THE BOARD

9. SCHEMES FOR ACQUISITION OF PROPERTIES - It being found that the acquisition of a few properties in addition to those already notified under the several Government Declarations in the Krishnaraj, Devaraj, Mandi, Lashkar and Nazarbad -- mohallas, was necessary for the further improvement of those areas, two supplemental acquisition estimates for Rs. 61,718/- and Rs.45,620/- involving respectively 174 and 72 properties were got up and passed by the Board during the year under report. Of these two estimates the first one was submitted to Government during the report year, and the second, -- subsequently.

10. SCHEMES FOR CONSTRUCTION WORKS OF PROGRAMME OF MARCH 1912 - In repect of the works relating to the Programme prescribed in Government Order No 6831-FL.136-11-7 dated the 21st March 1912, the following six estimates were passed by the Board during the year under report.-

(i) Modified estimate for laying pipe sewers in No.II. Drainage area for Rs.4,36,938/-, the amount of original estimate being P.3,09,067/-.

(ii) Supplemental estimate for sewering a portion of Ittigegud Drainage area, for Rs. 6,766/- this had been omitted to be included in the original project for Rs.55,205/- prepared and submitted during the previous year 1915-16

19

(iii) Estimate for the linking up of the Nazarbad storm water drain with the main storm water drain from Nos II, and III. Drainage areas, for Rs.3,990/-.

(iv) Estimate for constructing a storm water drain along the Sayaji Rao road in front of the Lothikhana, Mr.Banumiah's School and the proposed new Municipal Office site, for Rs.3,525/-.

(v) Estimate for constructing a storm water drain on the old Idga road of Nazarbad mohalla for Rs 973/-.

(vi) Revised estimate for paving the storm water drain of No.III Drainage area near the Hardinge Circle for Rs.13,100/-, in lieu of the original one sanctioned for Rs.10,106/-

11. SCHEMES UNDER PROGRAMME OF NOVEMBER 1914 - With regard to the Second Programme prescribed in Government Order No.3702-9/Ml.163-14-1 dated the 6th November 1914, the Board of Trustees passed the following estimates during the year under report -

(i) Modified estimate for improving the Devaraj market square for Rs.1,08,150/- subsequently raised to Rs.1,10,800/- This estimate relating to the structural portion of the scheme was a modification of a part of the combined estimate for Rs 4,48,035/- which included the cost of acquisition of the required properties and was referred to in sub-para (iii) of para 25 of the Board's Administration report for the year 1914-15.

Detailed plans and estimates for this work were prepared by Mr.S.H.Lakshminarasappa B.A.,B.E., Assistant Engineer, Head Quarters Range, Mysore.

(ii) Revised estimate for Rs.11,856/- for draining the marsh below Kukkarahalli tank in lieu of the estimate for Rs 9,170/- sanctioned in Government Order No.9265-71/ Ml.24-15-102 dated the 21st June 1916.

(iii) Estimate for laying out an extension on the Seringapatam road for Rs 2,22,600/-. The proposed extension being since found to be not popular, the estimate is withheld from being submitted to Government

(iv) Modified estimate for Rs 12,73,305/- for the proposed Comprehnsive Scheme for laying out the Vontikoppal extension, in lieu of the one passed by the Board for Rs.10,44,650/- in the year 1914-15. The estimate originally prepared for Rs.2,06,000/- for laying out a portion of this extension was also modified during the year, the estimated amount being raised to Rs.2,43,278/-.

(v) Supplemental estimate for completing the improvements to the junction of the Railway Station and Viceroy roads at the entrance to the Railway Station for Rs. 5,282/-.

(vi) Estimate for Improving the square in front of the south Fort gate at the junction of the Chamaraj road and the Doddkere tank

bund road for Rs.1,420/-.

(vii) Estimate for improving the junction of the Church road and the Railway Station road in front of the Arch Gate for Rs.768/-.

12. ADDITIONAL SCHELES PASSED BY THE BOARD - The following additional schemes and estimates were passed by the Board during the year under report.-

(i) Revised estimate for the improvement of the Devaraj market for Rs.1,19,640/-, the estimated cost of the original estimate being Rs.54,642/-.

(ii) Estimate for filling Benneharadanahalli feeder channel and draining the Lakshmipuram valley for Rs.23,990/-.

(iii) Comprehensive estimate for planting Avenue Trees on certain important roads of the Mysore City, for Rs.22,800/- in lieu of the original one for Rs.46,000/- A separate estimate for a part of this scheme amounting to Rs.5,000/- was prepared and submitted to Government for planting avenues on the Chamaraj, Krishnaraj and Hydergunta roads in the City and thier maintenance during the year 1916-17.

(iv) Estimate for laying out the grounds now occupied by the Bamboo Bazaar for ~~Rs.14,565/-~~ Rs.14,665/-.

(v) Estimate for cutting and grading roads and conservancy lanes and constructing storm water drains in the Jellington Lodge compound for Rs.9,830/-.

(vi) Estimate for repairs and maintenance of completed works for the year 1916-17, for Rs.3,500/-.

(vii) Estimate for improving and re-aligning the foot-path on the Sayaji Rao road in front of the Lothikhana and the proposed Municipal Office buildings, for Rs.2,392/-.

(viii) Estimate for constructing underground drains and diverting the surface water in the Statue Square, for Rs.410/-

15. Besides the above, the Board of Trustees approved an estimate for Rs.41,217/- received from the Executive Engineer, Water Supply Division, for laying mains and erecting fountains in the Chamundi Extension, and submitted the same for the sanction of Government during the year under report. This estimate formed part of the major estimate for laying out the extension sanctioned for Rs.1,12,348/- in Government Order No.7322-5/Ml 24-15-76 dated the 30th March 1916.

14. PROJECTS FORWARDED TO GOVERNMENT FOR SANCTION - The undermentioned 21 projects amounting to Rs.22,91,976/- were duly submitted to Government for sanction during the year under report -

No.	Name of project	amount of estimate
1.	Acquisition of certain shops and houses for improving the Devaraj market square.	Rs. 2,90,400
2.	Acquisition of certain supplemental properties in Krishnaraj, Devaraj, Lashkar and Mandi mohallas.	22,170
3.	Construction of Municipal Office buildings.	43,800

4.	Laying pipe sewers in No.III. Drainage area, part I.	under Contingencies	Rs. 1,13,128
5.	Laying pipe sewers in Ittigegud Drainage area	under Contingencies	55,205
6.	Construction of Lodel Houses.	C.L. 54-11-8	30,429
7.	Forming new foot-paths near the Memorial Fountain.	Mrl 24-16-12	570
8.	Acquisition of a portion of the Wellington Lodge compound.	Mrl 71-16-2	7,000
9.	Acquisition of certain supplemental properties in Krishnaraj, Mandi, Lashkar, Chamaraj and Devaraj mohallas	Mrl 71-16-9	61,718
10.	Comprehensive Scheme for Laying out the Vontikoppal extension (modified).		12,73,305
11.	Improvement of the Devaraj Market (revised)	Mrl 24-16-43	1,19,640
12.	Improvement of the Devaraj Market square (modified)	Mrl 24-16-31	1,10,800
13.	Planting avenue trees on certain important roads of the Mysore City (Revised Comprehensive Scheme)	Mrl 122-15-7	22,800
14	Draining the Marsh below Kukkarahalli Tank (revised)		11,856
15.	Cutting and grading roads and conservancy lanes and constructing storm water drains in the Wellington Lodge Compound	Mrl 23-17-20	9,830
16.	Completing the improvements to the junction of the Railway Station and Viceroy roads at the entrance to the Railway Station (supplemental).	Mrl 24-16-58	5,282
17	Repairs and Maintenance of completed works for the year 1916-17	Mrl 24-16-22	3,500
18	Improving and re-aligning the foot-path on the Sayaji Rao road in front of the Mothikhana.	Mrl 24-16-42	2,392
19.	Constructing a storm water drain on the old Idga road of Nazarbad mohalla	Mrl 24-16-55	973
20.	Improving the junction of the Church road and the Railway Station road in front of the Arch Gate	Mrl 23-17-3	768
21.	Constructing underground drains and diverting the surface water in the Statue Square	Mrl 24-16-53	410
			22,91,976

The first seven of these 21 projects were those of the year 1915-16 and belonged to the group of 10 estimates mentioned in para 20 of the previous year's Administration Report as not having been submitted to Government within that official year. Item No.8 was another project of the year 1915-16 but omitted

by oversight to be included in the above group. The remaining 13 were the estimates sent up for sanction out of the 23 estimates amounting to Rs.23,95,889/- passed by the Board during the report year only.

15. ESTIMATES SANCTIONED BY GOVERNMENT - Omitting the small estimate for Rs.500/- since held superflous but wrongly included in the year previous among the estimates sent up to Government, there were 13 estimates pending with Government at the close of the year 1915-16, as ennumerated below -

(i)	Estimate for clearance of the existing private houses in the Fort, for Rs.	Rs. 10,84, 000
(ii)	Comprehensive scheme for the lay out of an area of 1,037 acres in the Vontikoppal extension, estimated cost as revised . . .	Rs. 9,37,220
(iii)	Scheme for acquiring properties in the remaining portion of No IV. Drainage area, estimated cost.	Rs. 3,10,850
(iv)	Modified estimate for laying pipe sewers in No.V. Drainage area and linking up the main sewer of No V. Drainage area with the Out-fall sewer of the City for .	Rs. 1,55,810
(v)	Modified estimate for laying pipe sewers in Nazarbad Drainage area for	Rs. 1,06,176
(vi)	Rough estimate for laying out a Girdle road round the City for .	Rs. 52,845
(vii)	Estimate for slabbing the bed of the flood water drain near the Pardinge Circle up to the Pleasure Palace Culvert for . .	Rs. 10,106
(viii)	Estimate for planting Avenue trees for the ear 1915-16 for	Rs. 5,025
(ix)	Modified estimate for improving the surroundings of the Bowan's Bavady in the Northern arm of Doddakere for . .	Rs. 4,080

(x)	Estimate for acquiring a vacant site near the Bar Lines on the Seringapatam road for	Rs.	3,695
(xi)	Estimate for constructing three Octroi Cokad buildings at the entrance gates from Seringapatam, Nanjangud and Heggadadevanakote to the City for .	Rs	2,040
(xii)	Estimate for covering the storm water drain in front of the Girls' school on the Chamaraj road for . .	Rs.	1,256
(xiii)	Estimate for eradicating trees and scrub jungle from the Fort Rampart wall, Mysore City for	Rs.	516

Including the above 13, the number of estimates that required the order of Government was 34, the amounts whereof aggregated Rs.49,65,601/-. Out of these 34 estimates, 24 estimates amounting to Rs.21,69,523/- were sanctioned by Government during the year under report as mentioned in statement No.II appended.

16 During the year under report, the Government sanctioned besides, the undermentioned three acquisition estimates which were parts of the major schemes noted respectively against each .-

i Estimate for Rs.1,67,572/- for the acquisition of 31 properties in the Fort, being part of the major project for the clearance of all the existing private houses therein, estimated to cost Rs. 10,64,000/-.

ii. Estimate for Rs.4,618/- for the acquisition of 4 properties in the Devaraj mohalla, being part of the major project for the acquisition of 46 properties estimated to cost Rs.22,170/-

26

iii. Estimate for Rs 3,373/- for the acquisition of another 4 properties comprised under the above said major scheme for Rs.22,170/-.

Execution.

CHAPTER II. ~~EXTENSION~~.

PART I ACQUISITION AND DEMOLITION OF PROPERTIES

17. LAND ACQUISITION OFFICER - The Chairman of the Board of Trustees continued to do the work connected with the acquisition of properties for purposes of the Trust Board, during the year under report.

18 PROPERTIES DECLARED BY GOVERNMENT .- The number of properties that were declared by Government for acquisition for purposes of the Trust Board, during the year under report was 854, the bulk of them forming the properties in the remaining blocks of the Krishnraj and the Fort mohallas in No IV. Drainage area.

19 PROPERTIES ACQUIRED DUPING THE YEAR - The number of properties acquired during the year under report was 116 in all. The acquisition of 100 of these properties was effected under the provisions of the Land Acquisition Regulation and that of the remaining 16 properties, by agreement with their owners under the provisions of section 22 of the City of Mysore Improvement Regulation. The following table shows the distribution of the said 116 properties according to mohalls, with the amount of compensation awarded or settled for the same -

	Acquired under the provisions of Land Acquisition Regulation.		Acquired under the provisions of section 22 of the City of Mysore Improvement Regulation.		
	No.	Amount of compensation awarded.	No.	Amount of compensation awarded	Total Amount of compensation
	17	6,282		17	6,282

2. Lashkar.	3	3,948	5	1,438	8	5,386
3. Devaraj.	18	10,476	1	55	19	10,531
4. Krishnaraj	48	21,749	10	2,325	58	24,074
5. Fort.	5	22,641			5	22,641
6. Nazarbad.	9	3,548			9	3,548
Total	100	68,644	16	3,818	116	72,462

73 119
72 462
657

20. DESCRIPTION OF PROPERTIES ACQUIRED - The properties acquired during the year comprised 8 garden lands, one dry field, 27 vacant lands and 80 structures

21. COST INCURRED ON ACQUISITION OF PROPERTIES - The total expenditure incurred on account of actual payments made during the year under report for properties acquired was Rs.73,119/-, including Rs.657/- paid on account of certain properties acquired in the year previous, but the payment of compensation whereof had not been settled then.

22. RETROSPECT OF ACQUISITION WORK DONE - Statement No.III. appended to the report shows the number of properties acquired in respect of the several Improvement Schemes of the Trust Board, and the amount of compensation paid therefor from the formation of the Board to the end of the year under report. The figures entered in this statement under columns 5,7 and 14 against Lashkar and Landi mohallas, Devaraj mohalla, Krishnaraj mohalla Part I and Lazarbad mohalla required to be revised in view to eliminate (i) cases of part acquisition (ii), cases of undeclared properties acquired by ~~mutual~~ mutual agreement wrongly included among declared ones and (iii) properties, the acquisition whereof was since found unnecessary. The required rectification will be effected soon after the publication of the withdrawal Notification by Government in the Gazette for

which purposes lists in respect of properties in Mandi, Krishnraj, Nazarbad and Lashkar mohallas have been submitted to Government and the list relating to the properties in Devaraj mohalla is under submission. As the figures stand, out of 7,522 properties declared for acquisition, 5,614 properties were acquired up to end of the year, leaving 1908 properties for further acquisition. In the case of 624 out of these properties, which are involved in the Scheme for Improving the remaining portion of No.IV. Drainage area -- comprising the Katwadipur Agrahar houses, the Trustees made a detailed inspection of the properties and were of opinion that no acquisition proceedings need be taken in cases on which the owners would bind themselves to carry out the improvements desired Negotiations on these lines are being made with the owners of the several properties concerned. The properties to be acquired for the improvement of the Devaraj Larket Square as well as those to be removed within the Fort are costly ones. It is the insuffiency of funds allotted that has deterred the progress of acquisition work in respect of these two schemes which require early attention

23. REFERENCES TO COURT UNDER THE LAND ACQUISITION REGULATION DURING THE YEAR - In two out of the 100 cases in which awards were made under the Land Acquisition Regulation references were made to Court under section 18 of the said Regulation, as the persons interested in the properties concerned objected to the amount of compensation awarded. In both these cases viz., O.S.No 19 of 16-17 on the file of the Sub-ordinate Judge, Lysore, since transferred to the file of the District Judge, Lysore, and O.S No.22 of 1916-17 on the file of the District Judge, Lysore, decisions were not -- obtained during the year under report. In seven other cases, references were made to Court under section 30 of the Land Acquisition Regulation for the settlement of disputes as to

apportionment of the compensation awarded or as to the persons to whom it was payable.

24 REFERENCES MADE IN PREVIOUS YEARS - In the appeal preferred against the order of the Sub-Judge to the Chief Court in R.A.No.358 of 1915-16 referred to in para 32 of the Board's Administration Report for the year 1915-16, the Chief Court modified the award adopted by the Sub-Judge by enhancing the rate of compensation from Re 1/- to Rs. 1½/- per square yard and allowing the value of a tree. The net result of this modification was that against the amount of Rs. 27/- originally awarded for the property a sum of Rs. 38-8-5 was ordered to be paid for it.

25. In O S.No 15 of 1915-16 on the file of the Sub-ordinate Judge, Lysore, relating to the reference made in connection with the acquisition of a garden land from H.R.Srinivasa Murthi in the year previous, the Court awarded a decree for an enhanced compensation of Rs 584-13-11 against the original amount of Rs 338/-.

26 In O S No 16 of 1915-16 on the file of Sub-Judge, Mysore, relating to the acquisition of property No (2) 101 in block No.62 No IV Drainage area from Mr M.K. Krishna Iyengar, the Court confirmed the award originally made

27 In the case of another reference under section 10 of the Land acquisition Regulation made in the year previous which was taken upon the file of the Sub-Judge, Mysore, as O S No 52 of 1915-16, and subsequently as No 13 of 1916-17 on the file of the District Judge, the Court decided that the claimant Lokmaraja Pandit should get Rs. 17-10-6 over and above the sum of Rs. 2,000/- originally awarded.

28. DEMOLITION OF ACQUIRED HOUSES - The number of houses demolished during the year under report was 66 Of these 36 houses were removed by the Departmental task workers and the remaining 30 houses were pulled down by their original owners at their own cost. The demolition charges during the year amounted to Rs. 809/-.

PART II CONSTRUCTION WORKS OF THE TRUST BOARD -

29 EXECUTION CONTROL - Mr H.F Barker, L C.E , Assistant Engineer, who had long been connected with the Trust Board by his service under it for ever 12 years was transferred to the Palace Varamuth Department on 11th, January 1917. This officer, who was in charge of the execution of the construction works of the Trust Board from the year 1913-14 continued to be so during the report year also, till the date of his relief in this Department Subsequently, Mr H R.Venkatasubba Rao, B.A , L.C E , Assistant Engineer, whose services were lent from the State Public works Department, was placed in charge of the above work from 12th February 1917, the date on which he joined duty under the Trust Board. During the intervening period from 12th January 1917 to 11th February 1917, the Chairman himself had the direct executive control over all the works of the Board

30 WORKS ATTENDED TO - The number of construction works attended to during the year under report was 49 in all The names of these works and the amount expended against the estimate under each of them during a d up to end of the year under report are entered in statement No IV. appended Item Nos. 36 to 39 were works carried out by the Electrical Department, Nos. 40 to 45, b the Municipal Engineer, under the direct control of the Chairman of the Board of Trustees, the remaining ones being those attended

to by the Assistant Engineer of the Trust Board under the general supervision of the Chairman Ten of the works mentioned in the said statement, viz items Nos 36 to 39, 42, 44 and 46 to 49 were works carried out under direct orders of Government against the special allotment of Rs.25,000/- reserved out of the annual grant sanctioned for the Board's expenditure .

31 CLASSIFICATION OF WORKS - The 49 works referred to in the above para, comprising 26 new works of the year under report and 23 incomplete works of previous years may be classified as below -

class.	Number of works			Expenditure for 1916-17		
	New	Old	Total	On new works	On old works	total
Sewerage and drainage works	7	7	14	1,58,840	30,749	1,89,589
Works adding to the Public conveniences or attractions of the City	14	11	25	33,622	52,840	86,462
Works relating to extensions and residential areas of the City	1	2	3	120	30,362	30,482
Miscellaneous works	4	3	7	10,703	1,986	12,689
Total	26	23	49	2,03,285	1,15,937	3,19,222

32. SUMMARY OF PROGRESS UNDER SEWERAGE AND DRAINAGE WORKS -

The following is a brief account of the progress made under the several items of sewerage and drainage works undertaken during the year under report -

(1) Laying pipe sewers in No.III Drainage area part 1. - This was a new work of this class started in the year under report, pending sanction of Government to the estimate submitted for the

same. Sewers to a length of 26,239 running feet were laid in in this area with 186 manholes and 4 flush tanks The number of houses connections given was 279

Estimate	Rs. 1,13,128/-
year's outlay	65,963/-

(2) Laying pipe sewers in Nazarbad Drinage area.- This was another new work started during the year under report The sanction of Government to the estimate for this work also is awaited Nearly 19,600 running feet of sewers were laid with 173 manholes and 1 flush tank. The number of house connections given was 240

Estimate	Rs. 1,06,176/-
year's outlay	44,395/-

(3) Laying pipe sewers in Ittigegud Drainage area - This was another new work of this class Nearly 11,200 running feet of sewers of 7" and 1,900 running feet of 12" or in all 13,100 running feet of sewers were laid in this area, the number of manholes constructed being 93, flush tanks 11, ventilating shafts 9 and house connections 188 Estimate for this work also is pending sanction of Government.

Estimate	Rs. 55,205/-
year's outlay	30,800/-

(4) Laying pipe sewers in No. II Drainage area - This work was started in June 1917 pending submission of the estimate passed by the Board to Government for sanction Only a small length of 592 running feet of sewers was laid during the year under report with 56 house connections

Estimate	Rs 4,36,938/-
year's outlay	6,565/-

(5) Laying pipe sewers in No V. Drainage area - This work had for the most part been completed in the year 1915-16

that remained to be done necessarily was finished during the year under report, by laying sewers to a further length of 2,689 running feet Four additional manholes, 2 flush tanks and 10 ventilating shafts were also constructed, and 88 additional house connections were given during the year under report. As it has been decided that pipe sewers are unnecessary for the portion known as new Doddaholageri, it may be held that the sewerage work in this area is practically completed

Estimate	Rs. 1,55,810/-
year's outlay	10,338/-
Total outlay	60,693/-

(6) Laying pipe sewers in No.IV Drainage area - A work of previous years During the year under report 8,839 running feet of sewers were laid with 44 manholes, 8 flush tanks and 13 ventilating shafts The number of house connections given during the year was 391.

Estimate	Rs. 3,64,410/-
Year's outlay	8,134/-
Total outlay excluding write-backs to other works	2,54,255/-

(7) Laying out a sewerage farm with distributory channels - This was an unfinished work of the previous year practically completed during the year under report. The idea of opening an experimental farm departmentally has been given up The Farm land is ordered by Government to be leased out to private persons temporarily by dividing them into small plots.

Estimate excluding the amount for experimental farm	Rs. 30,560/-
Year's Outlay	6,330/-
Total outlay	21,104/-

(8) Laying pipe sewers in No III. Drainage area Part ii - An old work which had well nigh reached completion. In this area a few pipe lines are required to be laid, which is delayed on

39

account of certain properties on the lines not having been acquired Steps are being taken to acquire them. During the year under report, sewers to a length of 1,103 running feet with 3 manholes were constructed. Ninety eight additional house connections were also given

Estimate	Rs 1,24,497/-
Year's outlay	3,289/-
Total outlay	98,042/-

(9) Out Fall Sewer Works - This was a completed work of the year 1913-14 A small expenditure of Rs.416 was incurred during the year under report on account of cleansing the chambers of the septic tank, pay of Watchman and other sundry items.

(10) Flooring the storm water drain near the Hardinge Circle - This was a new work practically completed during the year under report

Estimate	Rs 10,106/-
year's outlay	9,401/-

(11) Covering a portion of Doddakere feeder channel on Chamaraja road - A new work taken up and completed during the year

Estimate	Rs. 1,256/-
Year's outlay	1,330/-

(12) Diverting the surface water near the Statue Square - A small work estimated at Rs.410/- sanctioned during the year It was completed at a cost of Rs.397/-

(13) Filling the eastern Fort Ditch and diverting storm water of Fort into Doddakere - An unfinished work of previous years completed during the year under report

Estimate	Rs 27,940/-
Year's outlay	2,214/-
Total Outlay	27,954/-

(14) Improvement of flood water drain in No.IV Drainage area - This was a completed work of the year 1915-16 A small expenditure of Rs.28/- was however, incurred during the year under report on account of certain arrears The total expenditure is Rs 26,187/- against the estimate of Rs.27,713/-.

33 UNDERGROUND PIPE SEWERS ETC ,LAID FROM COMMENCEMENT - Since the introduction of the new system of underground pipe sewers that is, from the year 1912-13 to the end of the year under report, nearly 2,38,505 running feet or 45.17 miles length of sewers have been laid in the different parts of the City, and about 4,498 house connections constructed Statement No.V. appended to the report shows the details of street sewers etc , laid up to end of the year 1916-17 For the efficient working of the underground sewerage system, water supply connections to the flushing tanks is absolutely necessary In view to supply this desideratum, an estimate for Rs 37,505/- prepared by the Executive Engineer, water Supply and Stores Division has met with the approval of the Board and the same will soon be submitted to Government after certain preliminaries regarding the amount ~~of~~ to be contributed by the Municipality towards the cost of the execution of the works and their maintenance. are settled.

34. PROGRESS UNDER WORKS OF PUBLIC CONVENIENCES OR ATTRACTIONS OF THE CITY - These comprise works relating to (1) certain public buildings (2) better arrangements for street lighting on some important roads of the City (3) removal of unsightliness in certain parts of the City (4) improvement of certain roads and road junctions and (5) planting of avenue trees on certain main roads. The progress under the several works of each of these groups is recorded below -

(1) Improvement of General market - This work was done started in the latter part of the year 1915-16. It was found necessary to effect certain changes both

in design and lay out of the s-talls and in their roofing materials, the height of the pillars being required to be raised from 8 to 11 feet. A revised estimate for Rs. 1,23,500/- for this work was therefore submitted to Government for sanction. The full supply of iron articles required for the work was obtained and the roofing of 3 blocks out of 6, and the masonry superstructure work of block 4 were completed during the year under report. The charge of this work was with the Municipal Engineer till the end of April 1917 when it was transferred to the Assistant Engineer of the Trust Board

Note

Estimate (revised)	Rs. 1,23,500/-
Year's outlay	30,462/-
Total outlay	40,604/-

(2) Construction of Municipal Office Buildings - This was a new work under-taken during the year. The Estimate was sanctioned in January 1917 The acquisition of properties on the site proposed for the location of the building was nearly completed, only 4 properties remaining to be acquired at the end of the year out of the 23 A compound wall with cast iron ornamental railings was constructed during the year under report in front of the proposed buildings. A third of the estimated cost of this work is to be borne by the City Municipality, viz.

Estimate	Rs. 1,43,800/-
Year's outlay	5,031/-

(3) Construction of Cotroi Cokad Buildings - During the year under report, the Government sanctioned

37

the construction of three Octroi Ookad buildings on the Nanajangud and Heggadadevanakote roads and at the Seringapatam road entrace gate to the City Buildings at the first and second mentioned entrances were constructed and the site for the Ookad at the Seringapatam gate was finally fixed.

Estimate	Rs 2,040/-
Year's outlay	1,272/-

(4) Installing lights in Prince Albert Victor road - A sum of Rs. 8,427/- was paid to the Electric Department during the year under report for substituting ornamental lamp posts for the temporary lights installed on both the sides of this road from Hardinge Circle to Statue Square. These lights have been put up

(5) Shifting Electric lights on Krishnaraj Road - A line of street lights existed in the middle of the road. This line was shifted to the edge of the outer road and the lights fixed at the inner edge of the foot paths This system was adopted to avoid the interference of the avenue trees with the street lighting circuit lines It is a decided improvement over the original system and is very much appreciated by the public A sum of Rs 2,939/- was spent on this work

(6) Shifting Electric lines on Vanivilas road - A sum of Rs 1,872/- was spent for shifting the lights on this road similar to those on Krishna Raj road (work No.5 supra)

21

(7) Shifting Electric lines on Dhanaraj road -

38

On this road also, the lights were shifted as in the above two roads at a cost of Rs. 1,122/-

The aggregate charge of Rs. 14,360/- on account of the above 4 items Nos 4 to 7 was met out of Rs. 25,000/- provided for works to be carried out directly under the orders of Government in the Budget of the Board of Trustees for the year under report. The same represents the net amount of the estimates prepared by the Electric Department, providing for constructing the new lines and dismantling the old ones, giving due credit to the materials of the old line.

(8) Filling in the western side of Northern arm of Dodkere - This was an old work that neared completion in the year 1915-16. Additional filling to the extent of nearly 6,000 cubic yards was made round the Bowan's Bavady. 53 cubic yards of rough stone revetment, 466 running feet of balustrade parapet wall and 247 running feet of iron railing were constructed for the Bavady during the year under report

Estimate	Rs. 24,510/-
Year's outlay	7,280/-
Total outlay	25,678/-

(9) Improving the Jeevanrao tank bed - An old work started late in the year 1915-16 This is charged to Special Grant of Rs. 25,000/- Two storm water drains were constructed with rough stone in the bed of the tank to drain the water courses, and the grounds were formed by cutting down the mounds and filling up

39

hollows.

Estimate	Rs. 5,800/-
Year's outlay	3,418/-
Total outlay	4,171/-

(10) Filling in the large gaps in the masonry parapet wall of the Fort.- This was a new work taken up and practically completed during the year under report, in consultation with the Architectural Engineer. The work chiefly consisted in repairing the parapet wall on the Rampart here and there and plastering portions of their faces

Estimate	Rs. 2,000/-
Year's outlay	1,125/-

(11) Dismantling Eastern Rampart wall of the Fort, Mysore - This was a work started in the year 1913-14 but stopped pending the improvements inside the Fort. During the year under report, since a portion of the Fort wall came down by itself during rains a breach was made in the wall at that place and charged to work

Estimate	Rs. 5,292/-
Year's outlay	1,006/-
Total outlay	1,261/-

(12) Repairs to Fort Rampart Wall at the Eeraungere Entrance - This was a work of previous year charged to the special grant of Rs. 25,000/- completed during the year under report.

Estimate	Rs. 3,000/-
Year's outlay	553/-
Total outlay	2,691/-

(13) Fixing curb stones on the new road to the South of the Masonic Lodge - A new work attended to during the year and charged to the Special grant of Rs. 25,000/-. The Municipal Engineer was in charge of this work.

Estimate	Rs. 3,450/-
Year's outlay	2,705/-

(14) Improving and re-aligning the footpath along the Sayaji Rao road in front of the new Lothikhana buildings and the proposed Municipal Office Building.- The original foot-path on this road was not parallel with the parapet and railing of the new Lothinkhana Buildings, with the result that the road was wide in some places than in others. This defect was set right. The road is reduced to a uniform width of 51 feet. This was a new work of the year.

Estimate	Rs. 2,392/-
Year's outlay	2,089/-

(15) Improving the Karanjee Tank bund road - an old work. The road surface was re-coated with metal The front revetment for a length of about 250 feet slipped during the heavy rains As there was water in the tank at the place, the revetting work could not be taken up during the year. The tank could not be drained in the interest of the extensive gardens below it

Estimate	Rs. 11,352/-
Year's outlay	1,713/-
Total outlay	10,371/-

(16) Improving Doddkere tank bund road - This was a work practically completed in the previous year. Certain minor works which were needed for the improvement of the tank were attended to during the year under report.

Estimate	Rs. 13,193/-
Year's outlay	872/-
Total outlay	13,916/-

(17) Forming foot-paths on Sayaji Rao road from Curzon Park north gate up to Memorial Fountain - This was another new work started and completed during the year. All the roads in the Curzon park have foot-paths edged with curb stones. Only the portion of Sayaji Rao road near the north gate of the park was without them. This want has now been supplied.

Estimate	Rs 570/-
Year's outlay	526/-

(18) Fixing curb stones along the new road to the north of Gun Shed - This was a work of the previous year charged to the Special Grant. A small expenditure of Rs. 188/- being payment an account of arrears was incurred during the year.

(19) Improving the junction to the north of Town Hall - A new work taken up and completed during the year under report, under the charge of the Municipal Engineer The improvements effected at this locality comprised the formation of foothpaths with neatly dressed curb stones on all the four roads

meeting at the square, the rectification of irregular curves and metalling of the roads. Estimate Rs 4914 Years outlay 4664

(20) Improving the junction of the Railway Station and Viceroy roads near the entrance to the Railway Station Compound - This was an incomplete work of the previous year completed during the year under report and consisted of only half the Circle. In execution the estimated amount of cost had to be exceeded owing to slight change in design and alignment. A supplemental estimate providing for this excess as well as for completing the Circle to the north towards and within the Railway Station Compound has been sanctioned by Government.

Estimate	Rs. 5,262/-
Year's outlay	2,554/-
Total outlay	3,541/-

(21) Improving the junction of Chamraj and Doddakere tank bund roads - This was an incomplete work of the previous year completed during the year under report.

Estimate	Rs. 4,660/-
Year's outlay	1,283/-
Total Outlay	4,577/-

(22) Improving the square in front of Fort south gate at the junction of Chamaraja and Tank bund roads - A work taken up and completed during the year. There were two roads leading from the south fort gate to the Chamraja road. They were abandoned and and only one road was opened in their place.

The whole square and the newly formed road were metalled Also a foot-path was formed by the side of Palace Karuhatti with curb stones of well dressed slab stones A four- light fitting was installed in this square by the Electric Department. The work has effectively improved the locality and forms part of a general scheme of improvements laid out for the inside of the Fort

Estimate	Rs. 1,420/-
Year's outlay	1,265/-

(23) Constructing circular masonry parapet walls at the junction of the Chamaraj road with the Viceroy and Krishnaraj roads - A work of the previous year charged to the special grant of Rs. 25,000/-. A sum of Rs. 500/- was spent on purchase of cast iron ornamental railings and Rs 172/- paid to Electric Department for installing light in the circles, during the year under report.

Estimate	Rs 1,570/-
Year's outlay	680/-
Total outlay	910/-

(24) Forming a new triangle with curb stones near the Cow Karuhatti along the Chamaraja road - Another new work in charge of the Municipal Engineer taken up and completed during the year under report to improve the broad square by the side of the Cow Karuhatti, the cost being debited to the provision of Rs. 25,000/- for special works

Estimate Rs.400/-
Year's outlay 397/-

(25) Planting Avenue Trees - In connection with the comprehensive scheme sanctioned for ---- Rs.22,800/- for planting Avenue trees on important roads of the City, Avenues were planted during the year on the Chamaraja, Krishnaraja and Hydergunta roads and maintained during the year This work was attended to by the Municipal Engineer

Estimate for the year Rs 5,000/-
Year's outlay 3,020/-

35. PROGRESS UNDER WORKS RELATING TO THE EXTENSIONS OF THE CITY

This group comprises three items of which only first forms the main item of progress of the year -

(1) Lay out of the Chamundi Extension - The out lay on this work up to end of the year 1915-1916 was Rs.671/-during the year under report, nearly 14,000 cubic yards of earth work was carried out for levelling grounds and formation of roads and cement concrete surface storm water drain to a total length of about 13,500 running feet were constructed, including the diversion of the Benneharadanahalli Feeder channel with road crossings and tunnels at the required places A small outlay was incurred on water supply, for want of which the construction of houses by purchasers of sites in this extension was being delayed An estimate for Rs 41,217/- prepared by the Waterm supply Department for

45

laying mains and erecting fountains to this e extension has since received the sanction of Government

Estimate	Rs. 1,12,348/-
Year's outlay	30,342/-
Total outlay	31,213/-

(2) Extension in the Bakshi Basappaji Urs Lango Garden - This is a portion of the Chamundi extension and its layout was completed in the previous year only, a small expenditure being incurred during the year under report, on account of payment of certain arrears

Estimate	Rs 12,646/-
Year's outlay	19/-
Total outlay	10,519/-

(3) Cutting and grading roads in a portion of the Wellington Lodge compound - Pending sanction of Government to the revised estimate for Rs.12,000/- for this work, a small expenditure of Rs 120/- was incurred on earth work during the year under report.

36 PROGRESS UNDER MISCELLANEOUS WORKS - The Progress under the seven items of work grouped under this class during the year under report is as below -

(1) Draining the marsh below Kukkarahalli tank - This was an important and a purely sanitary work undertaken during the year. It was started late in the year owing to the difficulty in securing contractors for the work, but was pushed on with all possible rapidity.

sluice was constructed in the old Kukkarahalli village tank bund and the water first drained off. 11,000 cubic yards of earth work for levelling and sloping the marshy grounds and 400 cubic yards of rough stone work for the open drains to drain the marsh, were carried out during the year under report. The estimate was revised omitting the jelly drains proposed in the sanctioned estimate, and providing in their place open rough stone drains. The project had been based on levels taken when the marsh was full of water and these were found to be incorrect. Fresh levels were taken and modified estimate prepared based on correct levels.

Estimate	Rs 9,170/-
Year's outlay	6,849/-

(2) Repairs and Maintenance of works executed by the Board.- Government having directed in their Order No.1103-4/Ml.138-15-4 dated the 5th August 1916 that till the Trust Board works are handed over to the Municipal Council after completion, the charges of their maintenance should be continued to be borne by the Trust Board, this has become a recurring item of expenditure of this Department every year. During the year under report the outlay on this head amounted ot Rs.3,438/- against the estimate sanctioned for Rs.5,500/-.

(3) Construction of Model Houses for the poor - The formal sanction of Government to the construction of 56 model houses at an estimated cost of Rs.30,429/- was obtained during the

97

year under report No new houses were - - constructed The cost of Rs 1,075/- incurred during the report year was in connection with the settlement of certain old claims of contractors on account of the 10 houses built in the year previous

Estimate	Rs.30,429/-
Year's outlay	1,489/-
Total outlay	12,155/-

(4) Removing the Health Camp Sheds - This was a work attended to and completed by the Municipal Engineer in the previous year Payment of arrears was settled during the year under report

Estimate	Rs.3,800/-
Year's outlay	650/-
Total outlay	4,231/-

(5) Erecting a compound wall to the Cremation ground.- Another completed work of the year 1915-16 executed under the charge of the Municipal Engineer The Expenditure on this work during the year represents payment on account of arrears

Estimate	Rs.1,337/-
Year's outlay	261/-
Total outlay	1,481/-

(6) Eradicating trees and scrub jungle from the Fort wall - Another recurring item of expenditure against the estimate sanctioned for Rs.516/- an expenditure of Rs 190/- was incurred during the year under report The work was attended to by the Park Overseer

(7) Survey charges - A sum of Rs. 225/- was incurred on this head during the year under report.

CHAPTER III. PROPERTY AND FINANCE.

Part I. INCOME FROM IMMOVABLE PROPERTIES OF THE TRUST BOARD.

37. INCOME FROM SALE OF EXPERIMENTAL HOUSES .- Out of Rs.1,361/- being the balance of cost of the 86 houses sold in previous years, a sum of Rs.475/- was collected during the year under report leaving Rs.903/- for future recovery. A sum of Rs.38/- was also recovered towards interest on unpaid balance of the value of these houses Statement No.VI. appended to the report furnishes particulars as to realizations from these houses from the commencement the Trust Board up to end of the year under report.

38. MODEL HOUSES.- There were seven model houses available for sale during the year under report. Six of these houses which including the value of site, cost Rs.9,559/- were disposed of during the year, in accordance with the terms of sale laid down by the Board of Trustees under which half the cost of structure and site was to be paid in advance and the balance within four years, in monthly instalments The number of houses disposed of altogether up to end of the year under report was 9 out of 10 constructed. The recoveries on account of these nine houses up to end of the year under report amounted to Rs.7,452/- of which Rs.5,762/- was adjusted by giving credit to the work itself, Rs.478/- was credited to the City of Mysore Improvement Fund account, and the balance of Rs.1,212/- held in deposit. Appended statement No.VII. shows the cost of each house sold and the recovery made towards the same up to end of the year under report A sum of Rs.9-5-0 was also recovered towards interest on unpaid balance during the year. Out of this sum, Rs.2-0-11 was by oversight written off as recovery, towards principal and given credit to the work

on this head during the year under report.

Survey charges :- A sum of Rs.856/- was incurred

CHAPTER III. INCOMES AND REMARKS.

Para 5. INCOME FROM MISCELLANEOUS SOURCES OF THE TRUST

SALES.

6. INCOME FROM SALE OF INSTRUMENTAL HOUSES:- Out of Rs.[illegible]/- being the balance of cost of the 25 houses sold in previous years, a sum of Rs.470/- was collected during the year under report leaving Rs.308/- for future recovery. A sum of Rs.38/- was also recovered towards interest on unpaid balance of the value of these houses. Statement No.VI. appended to the report furnishes particulars as to realisations from these houses from the commencement of the Trust Board up to end of the year under report for sale during the year under to ort. Six of these houses a

88. MODEL HOUSES:- There were seven model houses existing including the value of site, cost Rs.[illegible]/- were disposed of in the year, in accordance with the terms of sale laid down by the Board of Trustees under which half the cost of structure and site was to be paid in advance and the balance within four years in monthly instalments. The number of houses disposed of stood up to end of the year under report was 9 out of 10 constructed The recoveries on account of these in e ase up to end of the year under report amounted to Rs.[illegible]/- a sum of Rs.478/- was credited to the head of Improvement during the year and the balances of Rs.[illegible]/- held in deposit. Expenses attending sale of houses the cost of such houses sold during the year under report. Out of Rs.30-5-0 was also realised as [illegible] to the year under report a sum of Rs.[illegible]/- being the balance of cost of 25 houses sold in previous years, a sum of Rs.470/- was collected during the year under report leaving Rs.308/- for future recovery. A sum of Rs.38/- was also recovered towards interest on unpaid balance of the value of these houses. Statement No.VI. appended to the report furnishes particulars as to realisations from these houses from the commencement of the Trust Board up to end of the year under report.

88. MODEL HOUSES:- There were seven model houses existing for sale during the year under report. Six of these houses a

accordingly. This mistake will be rectified during the current year.

39 HOUSES REMAINING OUT OF THE ACQUIRED ONES - During the year under report, 46 new properties were added to the list of these houses which raised its number to 93. Out of these 93 properties, 14 were demolished during the year under report, and 2 were sold on the instalment payment system. There were thus 77 acquired properties left undisposed of at the end of the year 1916-17. It will be seen from statement No VIII appended to the report that out of Rs. 65,141/- being the value of the 146 houses sold up to end of the year under report, Rs. 62,166/- were recovered during the period, the actual realization for the year under report being Rs 293/-.

40 BUILDING SITES - During the year under report, 79 new sites were formed, 35 being in the Weavers' Lines, 25 in Krishnaraj mohalla, 11 on the Vanivilas road, and 8 in the Wellington Lodge compound. There were 1,207/- sites undisposed of at the beginning of the year belonging to the Trust Board in the several parts of the City. Including the new sites formed during the vear under report, the total number of sites that were available for sale was 1,286. Of those, 215 sites were disposed of both by public auction and private sale and 1,071 sites were left for future disposal The realisations from this item of income during the year under report amounted to Rs. 30,065/-, of which Rs. 5,464/- were credited in accounts towards the Improvement Fund, and the balance held in deposit pending the execution of the Kutcholika to start building operations by the parties concerned, in the form approved in Government Order No 1357-8/A1.230-15-4 dated the 15th August 1916. In the case of persons who have failed to execute the required Kutcholikas, as well as in the case of those who have not complied with the terms thereof, steps are being taken to resume the sites sold

58

Statement No.IX. appended to the report furnishes particulars as to the number of building sites sold up to end of the year under report, the amount recovered on account of their cost, and the amount of balance for future adjustment or recovery.

41 BITS OF LAND - The recoveries from the sale of small bits of land forming the surpluses of the acquired properties after their use for improvement purposes amounted to Rs.2,050/- during the ~~xxxxxx~~ year under report. Statement No.X. appended to the report shows the sale of these small plots of land from the commencement up to end of the year under report, the amount recovered on their account, and the amount remaining for future recovery.

42 LEASE OF LANDS - It was arranged to lease out the lands of the Sewage Farm temporarily for a period of 5 years, in accordance with Government Order No 1130-3 A/Ll.50-13-64 dated the 7th August 1916. The matter is under correspondence in the Municipality

43 TRANSFER OF TRUST LAND - A portion of the site reserved for the Kannada Normal School in the Lakshmipuram extension in the Mysore City, measuring 37,422 2/9 square yards and land measuring 19,296/ square yards required for the Mulbery Farm were handed over to the Director of Sericulture, under Government Order No.4578-83/A and E 49-16-15 dated the 14th December 1916.

44. FREE GRANTS OF LAND - The grant of the undermentioned lands free of cost was sanctioned during the year under report.-

(1) Site measuring 654 7/9 square yards in block No 12 to Rev. W Sawday for purposes of the Wesleyan Mission under Government Order No P426-7/Ll 97-16-2 dated the 19th October 1916.

(2) Site to the north of the Chamarajendra Technical Institute measuring 2,200 square yards for the

51

construction of the Saradavilasa Pathashala, under Government Order No.2428-9/Ml.93-16-2 dated the 19th September 1916.

(3) Site measuring 130 feet by 100 feet to the south of the Ladigakeri in the Jalapuri Extension for constructing a School building to the Hindu Depressed class Education Mission, under Government Order No.3617-8/Ml.138-16-2 dated the 5th December 1916.

(4) Site measuring (22' X 23') 56$\frac{2}{9}$ square yards in block No.18 to Luzawar Mahamud Ebrahim and others for the erection of a permanent structure for purposes of Loharum Festivities, under Government Order No.4014-5/Ml 146-16 dated the 26th December 1916

(5) Two strips of land measuring 3' X 50' and $\frac{8 + 5\frac{1}{2}}{2}$ X 24$\frac{1}{2}$' respectively in block No 11. Mandi mohalla to Sherifa Bee and Mahamud Sab as the same were very necessary for their buildings and the parties were too poor to pay for the same, under Board's resolution No XXIII dated the 29th January 1917.

(6) Site No 64 measuring 293$\frac{1}{3}$ square yards in the Brahmin block of the Chamundi Extension to one Gundappa, Santhepet, Mysore, under Board's resolution No.[illegible]. dated the 7th May 1917.

PART II FINANCE (CITY OF MYSORE IMPROVEMENT FUND)

11

45. Grant for the year - In addition to the normal grant of Rs.3,50,000/- the Government were pleased to sanction an additional grant of Rs.1,00,000/- in their Order Nos.6527-9/Ml

1C8-16-5 and 7572-3/Ll.1C8-16-5 dated ~~xxx~~ respectively the 9th April and 26th May 1917, so that the total amount allotted for expenditure during the year under report was Rs.4,50,000/-. This sum comprised the following -

(1)	Closing balance of the City of Mysore Improvement Fund for the year 1915-16	Rs	— 56
(2)	Sale proceeds of lands and buildings and other property belonging to the Board, realisations from rents and profits and re-payments towards House Building advances as detailed in statement No.XI. (appended)		36,042
(3)	Contribution from the Municipal Funds towards one-third cost of the Municipal Office building as approved in Government Order No.1435-7/Ll.24-15-119 dated the 22nd August 1916.		5,000
(4)	Amount placed by Government at the disposal of the Board during the year under report to make up Rs. 4,50,000/-		4,09,014
		Total Rs.	4,50,000/-

46 EXPENDITURE UNDER MAIN ITEMS - Against the above grant of Rs.4,50,000/- an expenditure of Rs.4,50,187/- was incurred during the year as detailed below -

(i)	On acquisition and demolition of properties	Rs	73,927
(ii)	On construction of drainage and other sanitary works including survey charges.		3,04,365
(iii)	On house building advances		39,999
(iv)	On establishment charges.		31,222
(v)	On tools and plant, printing refunds and Law Charges		674
		Total	4,50,187

47. HOUSE BUILDING LOANS - In accordance with the rules framed by Government under section 38 of the City of Mysore Improvement Regulation, loans amounting to Rs.42,625/- were sanctioned during the year under report to 141 persons. In 36 of these cases, the loans sanctioned exceeded R.200/- Including the amount that remained unpaid out of the loans sanctioned up to end of the year 1915-16, the total amount that was actually lent for hose building and other improvement purposes during the year under report was Rs.39,999/-.

48. REPAYMENT OF LOANS - The arrears of instalments that stood unrecovered at the end of the year 1915-16 was Rs.7,480/- and this, added to the instalments that fell due during the year under report raised the amount for recovery to Rs.20,655/-. Out of this sum, Rs.13,264/- were realised during the year under report leaving a balance of Rs.7,391/- for future recovery. Statement No.XIII. appended to the report shows the amount of loans granted by the Trust Board up to end of the year 1916-17, the amount of instalments that fell due and the amount actually recovered. The collections of the year showed an improvement over those of the previous year, the percentage of the arrears to the amount due in the report year being 12 5 against 16 in the year previous.

CHAPTER IV: OFFICERS AND SERVANTS OF THE BOARD

49. THE SCHEDULED STAFF:- In lieu of the Sub-Assistant Engineer sanctioned in Government Order No.6863-5/Ml 106-13-26 dated the 12th May 1915 the appointment of two Lower Subordinates i.e. one Sub-overseer on Rs. 50- 5/3 - 70-4-10 and another on Rs. 35- 5/3 - 45-4-10 was sanctioned in Government Order No. 2701-3/M1.14-16-8 dated the 1st November 1916.

50. CONSTRUCTIONS - In connection with the work connected with the acquisition and supervision of properties and recovery of amounts due to the Trust Board, the Government

54

sanctioned in their Order No.2420-1/Ml.14-16-17 dated the 19th October 1916 the entertainment of a temporary establishment costing Rs.124/- per ~~xxxx~~ mensem for the year 1916-17½ For assistaing the Sub-ordinate Engineering staff in supervising the construction works under progress for conserving the pipe ~~xxxxxx~~ sewers etc., and for watching the Board's stores, the entertainment of a separate establishment for the year under report within a money limit of Rs.3,252/- was sanctioned in Government Order No.2628-9/Ml.3-12-5 dated the 10th October 1917.

51. COST OF ESTABLISHMENT - The ~~xx~~ expenditure incurred on account of the salaries and allowances of the several sections of the establishment of the Board during the year under report was ~~xxxxxxxxxxxx~~ Rs. 31,222/- against Rs 30,224/- in the year previous. The cost of establishment formed nearly 7 per cent of the total outlay for the ye ar.

D Muthunandan

Chairman

15th October 1917

Mysore

E Campbell

Statement No 1

Mysore City Improvement Trust Board.

Statement showing the date on which the Trustees held their ordinary meetings during the year 1916-1917 and the number of Trustees present at each of those meetings

No	Date of Meeting	Number of Trustees present	Absent	Percentage of Trustees present	Remarks
1	31st July 1916	6	3	67	
2	28th August 1916	6	3	67	
3	25th September 1916.	7	2	78	
4	30th October 1916	7	2	78	
5	27th November 1916	7	2	78	
6	18th December 1916	9	.	100	
7	29th January 1917	6	3	67	
8	26th February 1917	7	2	78	
9	26th March 1917	8	1	89	
10	30th April 1917	7	2	78	
11	7th May 1917.	7	2	78	Adjourned meeting of 30th April 1917
12	28th May 1917	7	2	78	
13	25th June 1917.	8	1	89	

Average - 79 per cent for the whole year.

92 / 13 = 7.15 × 10

92-10 / 9 9 715

Mysore
Dt. 15 10 1917

Chairman

Secy

APPENDIX I

Rules of Procedure concerning the Board of Inquiry.

1870-74.

Statement.

J. W. [illegible] Esq. [illegible]

[illegible]

[illegible]

[

APPENDIX A.

Names of Trustees constituting the Board of Trustees for the Improvement of the City of Lyoore at the close of the year 1916-17.

CHAIRMAN.	1. Mr.T.Lakshmana Rao, L.C.E.,
EX-OFFICIO TRUSTEES	2. Dr.L.Srinivasa Rao, M.A.,M.D., Sanitary Commissioner.
	3. Mr.C.Narayana Rao, B.A.,B.L., Vice-President.
	4. Mr.A.K.Rami, D.P.H., Health Officer
TRUSTEES APPOINTED BY GOVERNMENT.	5. Mr.E.E.Campbell, I.C.S.,C.I.E.,
	6. Mr.L.Venkatakrishnaiah,
	7. Mr.Mahamad Jaffer Sahib.
TRUSTEES ELECTED BY THE MUNICIPAL COUNCIL AND APPROVED BY GOVERNMENT.	8. Mr.A.C.Ranga Iyengar, B.A., Rao Bahadur.
	9. Mr.L.Ananthrajiah.

Chairman,
City Improvement Trust Board,
Lyoore.

Lyoore
Dt: 10-4-1917

Mysore City Improvement

Statement showing the Estimates sanctioned &

	Name of Estimate
1	Estimate for filling the grounds near Bannes
2	Estimate for Acquiring vacant land &c near th Known to belong to Khanulla Khan
3	Estimate for improving and curing a portion of feeder channel on the Chamaraj road in front of
4	Estimate for the removal of plants on the fort &
5	Estimate for the Acquisition and demolition of prop Connection with the improvement of of the Dewan's
6	Estimate for opening out a girdle road round the
7	Estimate for fixing curb stones near Memorial Fou
8	Paving the bed of the 8 bore water drain near the
9	Estimate for constructing 3 coolie buildings
10	Estimate for the acquisition of a portion of the Wellington Lodge Compound
11	Estimate for repairs and maintenance to works const
12	Estimate for laying out a complete pipe Sewerage for No V Drainage area
13	Estimate for the acquisition and demolition of prop. fort and Krishnaraja Mohalla
14	Estimate for improving and re-aligning the foot path on road in front of the New Mothikhana

...t Board

Government during the year 1916-17

	Amount	Government order Number	Government order Date	Remarks
...inary	4086	102-4 and ~~24-15-52~~ 24-15-110	6-7-16	
Barn lane	3695	639-40 and 57-15-52	19-7-16	
...thes doubtless				
...e new girls school	1256	801-3 and 24-16-2	25-7-16	
...apart wall	516	1196-1200 and 24-16-6	9-8-16	
...this m...				
...ket square	296,400	1281-2 and 24-16-8	12-8-16	
...ity	52,845	1652-4 and 24-15-121	30-8-16	
...lane	570	1760-2 and 24-16-12	-9-16	
...ange circle	10106	1775-7 and 24-15-122	7-9-16	
	2040	1801-3 and 24-16-3	8-9-16	
	7000	1933-6 and 71-16-2	16-9-16	
...ted by the Board	3500	2324-6 and 24-16-20	17-10-16	
...stem	155810	2783-5 and 24-16-28	6-11-16	
...ties m...	310850	3650-1 and 24-15-125	6-12-16	
Sayaji Ro...	2392	4170-2 and 24-16-40	4-1-17	

5 Estimate for the construction of the new
Estimate for laying out Vankikoppal Extension.
7 Estimate for constructing model houses
8 Acquisition of certain properties in Blocks
87, 2, 9, 13, 18, 19, 20, 21 & 22, 24, 25, 27, 28, 34,
49 and 54
1 Estimate for diverting the storm water at the
20 Estimate for improving the storm water drain
— old Idga road of Nazarbad Mohalla
21 Estimate for improving the approach to Railway
the junction of the Railway station and Viceroy Rd
22 Estimate for the comprehensive scheme for pla
Avenue trees
23 Planting Avenue trees for the year 1915—16
~~do — do — 1916—17~~
24 Estimate for Constructing new Buildings round
Devaraj Market Square

Part Sanctions of Major Sch

1 Estimate for the acquisition of 4 proper
Devaraj Mohalla
2 Estimate for the acquisition of 4 properties
Devaraj Mohalla
3 Estimate for the acquisition of 31 properties
X
4 Estimate for planting Avenue trees for the year 1916-1

	143,800	4263-6	24-16-41	8-1-17
	9,37,220	4364-6	24-15-	11-1-17
	30429	4926-7	57-14-81	30-1-17
	61718	6291-2	71-16-9	20-3-17
	410	6524-5	24-16-53	9-4-17
	973	6957-8	24-16-53	2-5-17
	5282	7287-9	24-16-58	17-5-17
	22,800	7705-7	142-15-27	7-6-17
	5225	do	do	do
	5000			
	110,800	8062-4	24-16-62	22-6-17
	21,69,523			
	4618	2783-5	24-16-28	6-11-16
	3373	5358-9	24-16-49	15-2-17
	167,572	6017-9	24-15-128	15-3-17
	5000	7705	142 15	7 6 17

Part of major scheme for Rs 22,170/-

Part of major scheme for Rs 22,170/-

Part of major scheme for Rs 10,84,000/-

Part of major scheme for Rs 22000

Estimates Coming under Special grants

1 Estimate for running separate m.c. concrete street lighting cuverts on the right side of the Krishnarayapuram Vanniyar road.

2 Estimate for forming a new triangle with curb stones the side of Karukattur

3 Estimate for putting curb stones on either side of the road newly opened to the south of Maroor Lodge.

Taxpayer

Dated 15-10-17


2939
1872
2221-3 wk 24 16
7-10-16
7-10-16
400
2236-7 wk 24 16
11-10-16
3450
2423-5 wk 24 16 26
19-10-16

Statement.

Municipality Improvements &c.

Statement showing the number of properties acquired and [illegible]

Head of Charge	Declared to be acquired		Proprietors out of those declared	
	No. of properties	Estimated Cost Rupees	upto end of 1915-16	1916-17
2	3	4	5	6
Acquisition of properties in Lashkar and Fort by Mahals	2688	3564505	2528	20
— do — in Siva Raja Mahalla	1303	392972	616	18
— do — in Krishna Raja Mahalla part I	467	95852	416	16
— do — for Creating a Side for the Conservancy & Municipal Office Building in No 55 Krishna Raja Mahalla	27	28865	—	4
Acquisition of properties in Chamaraja Mahalla	902	167621	882	—
— do — in Fort	405	780192	361	5
— do — in Nazarbad Mahalla	448	87782	431	9
— do — in No IV D A Camp comprising Blocks 75, 77, and 69B	551	101431	236	22
— do — outside the area operated upon by the Trust Board	35	43805	35	—
Acquisition of Sunkey fields for outfall Sewer works	53	18300	9	—
Acquisition of properties for the Improvement of the Devaraja Market Square	19	296400	—	
— do — in blocks No 72, 73, 66, 74, 75 and 76 of Fort Mahalla and Nos 67, 77, 80, 82, 83 and 85 in Krishna Raja Mahalla	624	310550	—	6
Stone ware pipes	—	—	—	
Weavers' Sheds	—	—	—	
Open Air Camp	—	—	—	
Chamarajapuram Extension	—	—	—	
Total	7522	2680525	5514	10

Checked by

Effected as per Sanction Chief Secretary's Memo No 1916-17

(5)

Balance forward up to the end of 1916-17

Lands acquired				Amount of Compensation paid			Number/Area of the claims received during the year 1916-17	Remarks
To Govt. Department		Total						
up to end of 1915-16	During 1916-17	up to end of 1915-16	During 1916-17	up to end of 1915-16	During 1916-17	Total		
7	8	9	10	11	12	13	14	
674	5-	3202	25-	3843547	11867	3962214	140	
32	1	648	19	1746006	10619	1846625-	669	
96	6	512	22	1116673	57778	1,174451	3	
-	-	-	4	-	6772	6772	23	Awards have been passed in 19 other cases
32	"	914	"	1326760	"	1326760	20	
6	"	367	5	6287320	225584	6,512316	39	
186	"	617	9	833030	37774	870804	5	
30	3	246	25-	541460	75518	616664	293	
-	-	35-	-	411848	-	411848	"	
-	-	9	"	74688	-	74688	44	
-	-		-	-	-	-	19	
-	1	-	7	-	42097	42097	618	
2	-	2	-	7340	-	7340		
2	-	2		2120	"	2120	-	
4	-	4	-	38420	"	38420	-	
1	-	1		2000	-	2000	-	
1,065-	16	6579	116	1623621	73,119	16,96,740	1908	

2 Being the amount of awards during the

Lakshmana Rao
Chairman

Mysore City Improvement Trust Board

STATEMENT NO. IV

61

Statement showing the expenditure incurred on construction works during the year 1916-1917

	Name of work.	Amount of Estimate	Expenditure during 1916-17			Total up to end of 1916-17		
		Rs	Rs	as	p	Rs	as	p
	Construction of Municipal Office	1,43,800	5,031 (9)	0	0	5,031 (9)	0	0
	Laying pipe sewers in No III drainage area part II	1,24,497	3,288 (10)	14	5	98,042	8	7
	Construction of outfall sewer works	1,04,723	415 (12)	11	9	1,02,018	4	2
	Laying out sewage farm with distributory channels at the end of out-fall sewer	41,480	6,329 (13)	11	10	21,604	5	8
	Filling in tthe western portion of northern arm of Doddakere	24,510	7,279 (14)	14	1	25,678	3	11
6	Laying pipe sewers in No IV drainage area	3,64,410	8,134 (14)	0	0	2,54,255	5	10
7	Laying out Bhakshi Basappaji Urs garden extension	12,646	19 (15)	1	0	10,518	10	10
8	Laying pipe sewers in No V drainage area	1,55,810	10,338 (16)	2	10	60,693	1	4
9	Construction of Model Houses.	30,429	1,489 (24)	0	0	6,428	5	2
10	Survey works		226 (31)	6	1	1,379	1	
11	Improving the Doddakere tank bund road	13,193	872 (17)	3	0	13,915	13	
12	Improving the Karanji Tank bund road	11,352	1,713 (18)	3	2	10,371	6	
13	Improving the junction to the north of Town hall	4,914	4,663 (21)	8	0	4,663	8	
14	Covering a portion of Doddakere feeder channel on Chamaraja road	1,256	1,330 (25)	7	0	1,330	7	
15	Repairs and Maintenance	3,500	3,438 (32)	1	4	6,751	12	
16	Improving the junction of the Railway Station and Viceroy roads near the entrance to the Railway station compound	7,324	2,553	14	3	3,541	7	
			Carried over	57,123	2-9			

Brought forward 57,123-2-9

Laying pipe sewers in Ittigegud Drainage area		(39)	30,799	15	1	30,799	15	1
Laying out Chamundi Extension	1,12,348	(41)	30,342	6	0	31,212	13	10
Laying pipe sewers in Nazarbad drainage area		(43)	44,395	4	10	44,395	4	10
Draining the marsh below Kukkarahalli tank	9,170	(44)	6,848	8	6	6,848	8	6
Filling in the large gaps in the masonry parapet walls of the Fort	2,000	(45)	1,125	0	0	1,125	0	0
Improving the junction of the Chamaraja and Doddakere tank bund roads near the police out post	4,860	(46)	1,282	12	10	4,576	13	6
Filling in the eastern Fort ditch and diverting the storm water of the Fort into Doddakere tank	27,940	(48)	2,213	10	0	27,953	9	11
Eradicating the trees and scrub jungle from the Fort wall	516	(49)	190	7	1	190	7	1
Laying pipe sewers in No III Drainage area part I.		(50)	65,962	11	2	65,962	11	2
Forming foot paths on Sayaji Rao Road from the Curzon park north gate up to the memorial fountain	570	(1)	526	4	0	526	4	0
Improvement of flood-water drain in No IV drainage area	27,713	(53)	27	4	11	28,186	6	8
Diverting surface water near Statue Square	410	(55)	386	10	6	386	10	6
Dismantling the Rampart wall on the eastern side of the Fort	5,292	(57)	1,005	8	6	1,260	12	5
Improving and realigning the foot path along the Sayaji Row Road in front of New Kothikhana and proposed Municipal Office building	2,392	(47)	2,088	0	0	2,088	0	0
Constructing Octroi Oakad buildings	2,040	(3)	1,272	4	0	1,272	4	0
Flooring the storm water drain near the Hardinge circle	10,106	(2)	9,400	14	10	9,400	14	10
Laying pipe sewers in No II drainage area		(62)	6,565	3	6	6,565	3	6
Carried over			26,155	8	6			

		Brought forward			261555-6-6				
	Forming roads at the Fort south gate	. .	(63)	1265	14	-	1,265	14	0
				~~1,010~~	~~14~~	~~0~~			
35	Forming roads in the Wellington Lodge compound	.	(64)	1010	14				
				120	0	0	120	0	0
36	Shifting Electric lines on Krishnaraj roads	2,939	(21)	2,939	0	0	2,939	0	0
37	Shifting Electric lines on Venivilas road	1,872	(24)	1,872	0	0	1,872	0	0
38	Shifting Electric lines on Chamaraja road	9,706	(51)	1,122	5	3	11,504	12	3
39	Installing lights in Albert Victor road from Hardinge circle to Statue Square		(66)	8,427	0	0	8,427	0	0
40	Improvement of Devaraja market	1,23,500	(23)	30,462	6	11	40,603	12	11
41	Planting avenues	22,800	(38)	3,020	0	1	8,101	14	9
42	Fixing curb stones on the new road to the south of Masonic Lodge	3,450	28	2,704	12	0	2,704	12	0
43	Erecting a compound wall to the cremation ground	1,337	(54)	260	15	2	1,480	15	2
44	Forming a new triangle with curb stones near the cow Karohatti	400	(27)	396	15	6	396	15	6
45	Removing Health Camp sheds	3,800	(57)	650	6	1	4,231	13	9
				~~650~~	~~15~~	~~6~~			
46	Improving the JeevanRao tank bund road	5,800	(30)	3,417	12	0	4,170	14	0
47	Repairing and Improving the Fort rampart wall at the Eranagere entrance	3,000	(31)	552	13	0	2,691	6	0
48	Constructing circular parapet walls with ornamental railings at the junctions of Chamaraj & Viceroy roads & Chamaraj and Krishnaraj roads	1,570	(60)	680	4	0	910	3	0
49	Fixing curb stones to the new road to the north of Gun Shed	1,060	05	188	3	0	1,005	3	0
			Carried over	319636	11	6			

21

Brought forward 3,19,636-11-6

Deduct -

(1) Amount written back to other heads from the outlay debitted to laying pipe sewers in No. IV drainage area in previous years	9,525	0 0
(2) Amount credited to works out of realisations from sale of Model Houses	5,726	0 0
(3) Amount written back to other works from the booked outlay on forming Hardinge Circle	20	0 0
Total deductions	15,271	0 0
Net Expenditure	3,04,365-11-6	

CHAIRMAN.

Comptr

9525-3-3
5726-7-4
20-3-7
15271-14-4

3,19,636-11-6
15271-14-4
3,04,364-13-2

3,19,636-11-6
3,19,410-5-5
226-6-1

Statement

Mysore City Improvement

Statement Showing the length of pipe Sewers laid
Of the year 1916 – 17

	Area	Dimensions of Pipe 15"	12"		
1	laying pipe Sewers in No III drainage area (Part II)		481	233	44
2	do – Behind Bungalows on Yelwal				
3	constructing main out fall Sewer lines:				
4	ng pipe Sewers in No 5 Drainage area Bay Street				1116
5	do – Bazzaru's Lines				
6	Extending No II drainage area Main		188	1096	
7	Sewers in Laxmipuram Extn				3
8	– do – to tap the Sewage of Govt house				16
9	– do – do of Motor Garage Compound.				22
10	– do No IV Drainage area: Bakshi Bazar Project Sewers	96	1579	40	89
11	– do ~~B.B~~ garden Lands extension	–	–	–	3206
12	– do to tap the Sewage of Technical	–	–	–	921
13	– do No 5 Drainage area		–	4183	221
14	out of Sewage farm works distributory Channels	–	–	–	–
15	Laying pipe Sewers in Nazarbad Drainage area	–	–		196
16	– do Hige goad Drainage area	.	1979	–	111
17	– do No II Drainage area	–	–	–	5
18	do – No III Drainge area Part.	–	–	–	26
	Total	96	4227	5552	22760

Compd.

Board
fete
Ten Conductors in the several parts of the City up to the end

Total length	No of Lamp holes Conductors closed	No of Lamps Connections	No of Branch Lamps	No of Ventilating Shafts	Length of Gratings Sewers	½ Channel Pipes 9"	6"
46299½	295	1068	16	10			
2464	14		1	2			
	12				6022		
1110	4	6					
2259	15	33	2	2			
1782	6	104					
1381	10	20	1	1			
1680	11	2	1	1			
229	2	3					
9125½	583	2113	36	24			
3296½	21		2	3			
931	5	20					
26354	141	422	18	15			
						2981½	664
1961 2	173	240	1				
13104	93	188	11	9			
592	56						
26239	186	279	4				
235505½	1627	4498	93	67	6022	2981½	664

Chairman

Statement

Mapusa Cuty Dumpsite

Statement showing the particulars of Expenditure

upto 30 June of 19

Area	Number constructed upto end of 1916-17	Sold				
		upto the end of 1915-16		During 1916-1917		Le
		No.	value	No	value	No
1	2	3	4	5	6	7
Idga Design No. I	30	30	6,707	-	-	30
— do — do II	24	24	5,498	-	-	24
— do — do III	8	8	3,985	-	-	8
Total	62	62	16,190	-	-	62
Jail apsua Design No I	8	8	1,171	-	-	8
— do — do II	16	16	1,500	-	-	16
Total	24	24	2,671		-	24
Grand total	86	86	18,861	-	-	86

Form No. VI

Irish Church Board

50

Churches constructed by the Board and their disposal during 1917.

Name of Church	Area in square feet	Accommodation: Sittings provided during 1916-1917	Accommodation: Total Sittings	Balance of Grant to be received	Number of sittings taken up and paid for during 1916-17 by persons not members of the Church of Ireland	Remarks
1	2	3	4	5	6	7
Ballyhaise						
Ballyjamesduff						
Ballymachugh						
Ballyvaughan						
Bawnboy						
Belturbet						
Bruse						
Cavan						
Cloverhill						
Corlough						
Crosserlough						
Drumlane						
Drumlumman						
Drumreilly						
Dunmakeever						
Farnham						
Kilbride						
Killeshandra						
Killinkere						
Kilmore						
Kilnaleck						
Knockbride						
Lavey						
Mullagh						
Munterconnaught						
Shercock						
Stradone						
Swanlinbar						
Templeport						
Tomregan						
Urney						
Virginia						
Total						

Chairman

Mysore City Improvement

Statement showing the particulars of model houses up to the end of the year 1916 - 1917

Locality	Number remaining unsold up to the end of 1916-1917	Sold up to end of 1915-16 No.	Sold up to end of 1915-16 Values	Sold 1916- No.	Sold 1916- Values
	2	3	4	5	6
Vanivilas Road (Design No. 4) Krishna Raja mohalla	2	1	2023	1	194
Site of Bakki villas (Design No. 4) Niraraj mohalla	1	1	2652	5	
Mahaval Ramaiahs Street (Design No. 4) Niraraj mohalla	1		.	1	2621
Lashkar mohalla near Body guard lines (Design No. 3)	1	1	1114	5	.
Bande seri (Design No. 4) Krishna Raj mohalla	1	.	.	.	1
Idga (Design No. 3)	1	.	.		1 1071
Bhakshi Baraiappa's garden (Design No. 193)	2	.	.	.	1 994
Bridge, gud (Design No. 3)	1	.			1 956
Total	10	3			

Comptr

: Trust Board

Constructed by the Board and then disposed

| Land | | | Revenue | | |

Statement

Mayo no city Improve...

Statement showing the particulars of properties
after ...ing portions required for ...

1916 — ...

No	Area	Total number of ground portions available for disposal up to end of 1916-17	Sold		
			up to end of 1915-16		during 1916
1	2	3	4		
1	No. I drainage area	34-38	29	33024	0
2	No. II drainage area	100	81	148247	
3	No. III drainage area part i	13	11	41570	
4	No. III drainage area part ii	22	5	8470	
5	No. IV drainage area				
	Mahim Raj mahalla	19	7	6558	0
6	Shaikh Bhai drainage area	8	5	8888	0
7	Navgaon drainage area	6	6	12369	0
8	Mahim Raj mahalla				
	Corresponding portion 67a, 68, 69	35	0		2 10
9	Flat	1	0		0
	Total	238 237	144	801469	2 10

Compound

			Increase						
	Total		Total up to end of 1915-16	During 1916-17	Total	Balance not yet recovered	Recoverable during the year 1916-17	Remarks.	
	6		7	8	9	10	11	12	
	29	3304	0	0	0	0	4		
	18	1127	0	0	0	0	2		
	11	1450	0	0	0	0	2		
	5	840	0	0	0	0	1		
	7	1350	0	0	0	0	1		
			57 12-3	293-3-3	57116-3-3	2,974-3-4			
	5	888	0	0	0		0		
	6	1239	0	0			0		
3-4	2	1032-13-4			0	0	20		
	0	0		0	0		1		
4	146	65140-13-4	57123	293-3-3	57116-3-3	2974-3-4	44		

(1) Excludes a sum of Rs 4750/- recommended for remission by the collector as irrecoverable during the year (one of items 5 and 13 of item 8

Chairman

Mysore city Improvement

Statement showing the particulars of Building

end of 1915-16

No.	Drainage Area	Length of Line formed up to end of 1915-16	up to end of 1915-16		
			No	value	No
1	2	3	4	5	6
1	No I Drainage Area	2.58			
2	No II Drainage Area	115	91	17,7	
3	No III Drainage Area part	44	44	31,31.6	
4	No III Drainage Area part	10	6	911	
5	No IV Dr. Area Sunthuray	177	94	14,914	
6	No V Drainage Area	23	18	1,594	5
7	Bhagavad Drainage Area	79	69	4294	7
8	Nazarbad Drainage Area	143	140	6,514	
9	Idga Drainage Area	584	451	10,345	12
10	Laxmipuram extension	43	43	15,159	
11	Sahukar halli extension	1,050	737	25,89	1
12	Weaver's Lanes	150	96	5029	32
13	Old Idga extension	182	78	1,401	2
14	Galapuri extension	198	124	372	
15	Woda Halagere extension	944	575	18,190	
16	Shaksha Bahadoor's garden	66	18	1,383	
	Total	4,093	2804	163,164	215

31

Con

No. IX

... Trust Board

... formed, sold and available for sale up to

			Total	Revenue					
			No.	Value	up to the end of 1915-16	during 1916-17	Total	Returns up to the end of the year	Amount of sales cumulated at the end of 1916-17	Remarks
			8	9	10	11	12	13	14	15
			240	5,280					12	
			101	2,967					14	
			47	3,316					4	
			6	911					74	
			103	1,379					64	
			18	4,917	15,963	4,964	15,963	31,632	3	
			76	4,934					3	
			140	4,914					121	
			263	10,624					137	
			43	1,959					82	
			81	31,269					102	
			128	10,007					74	
			80	1,439					398	
			124	372					47	
			5,476	18,211						
			19	1,349						
			3,022	174,569	157,261	9,964	167,225	31,632	1,041	

Cost from Rs 24,624/- was duly received, which amount has been duly credited to the Trust Board.

Chairman

Statement showing particulars of lots of Mysore City Imp

No.	Drainage area	number	Lots of land up to end of 1915-1916		1916-
			Acs.		Ac.
1	2	3	4	5	6
1	No. I Drainage area				
2	No. II Drainage area	275	165	6.00	
3	No. III Drainage area (Part i)	175	134	14,089	
4	No. III Drainage area (Part ii)		24	1,268	
5	Ittigegud Drainage area	62	21	5	5
6	Nazara bad Drainage Area	141	81	2,622	5
7	New Idga ~~Drainage area~~	5	5	300	.
8	old Idga ~~Extension~~	9			.
9	Weavers Lines	4	3	16	3
10	Venkataraja mohalla	83	41	2,728	12
11	Chamarajapuram Extension	2	1	9	1
	Total	1,173	665	30,425	95

Compared

Statement No. X

Trust Boards.—

Land sold and available for sale up to end of 1916-1917.

Total		Recoveries up to end of 1915-1916	Recoveries during 1916-17	Total Recoveries	Balance to be recovered	Number now available at the end of 1916-1917
	value					
9		10	11	12	13	14
01	3,253					179
11	6,700					64
34	14,089					41
30	1,526					2
26	696					36
86	2,494					35
5	300	26,944	2,050	28,894	3,679	0
4	37					3
8	90					1
53	3,368					30
2	23					0
760	32,573	26,944	2,050	28,894	3,679	413

Chairman

Extract

C

Mysore City

Abstract account of Receipts and Expenditure of the M

Sl No	Receipts	Amount	Total
1	2	3	4
1	Opening balance	56 . .	56 . .
2	Sale proceeds of Lands & buildings and other properties belonging to the Board, realisations from rents & profits and repayments towards house building ~~Loans~~ advances (As per Statement No: XL)	36,042 . .	36,042 . .
3	Contribution from the Municipal funds towards one-Third Cost of the Municipal office building	5,000 . .	41,042 . .
4	Grant from Government	4,09,014 . .	4,09,014 . .
			4,50,000 . .

232-15-5
10-4
Grand Total
31-4-0
73-13-9

Compared

Fund No: XII

Improvement Trust Board

of the City Improvement Trust Board during the year 1916-1917

No	Expenditure	Amounts	Total
5	6	7	8
1	Acquisition and demolition of properties	73,927 6 3	
2	Construction of drainage & other Sanitary works including Sundry Charges	3,04,364 13 2	
3	House building Loan	39,999 2 2	
4	Establishment Charges	31,221 14 3	
5	Tools & Plant, printing, refunds and Law Charges	673 13 9	4,50,180 17 7
6	Closing balance	-187 1 7	-187 1 7

3,44,767-3-8
33298-9-6
226-6-1
37829-2-5

3 04 364-13-2
73927-6-3
37829-2-5

Chairman

Statement

Mysore City Dr

Statement showing the Amount of Loans & the Amount of Instalments of principal Actually received thereagainst

Nº	Names of residential Areas	Loans Up to end of 1915 - 16				Loans During 1916 - 1917			
		Nº	Amount			Nº	Amount		
1	2	3	Rs			5	Rs		6
1	Idga Extension	81	5 831	5	5	5	950	-	
2	Jalapuri Extension	26	1,731	6	-	1	500	-	
3	Nº I Drainage Area	71	5,782	3	1	16	2,649	2	
4	Ittegegud And Nazarbad	32	4,594	13	9	6	1,300		
5	New Dodda Holagere	116	3,745	-	-	"	"	"	
6	Chattanahalli Extension	122	20 328	2	-	49	14,600	-	
7	Nº II Drainage Area	39	9,435	13	10	11	2,350	-	
8	Krishnaraja Mohalla	56	14 990	-	-	39	13 300	-	
9	Nº III Drainage Area	19	5,650		-	2	1,600	-	
10	Nº IV Drainage Area	28	6,906	14	2	12	2,750		
	Total	590	81,025	12	3	141	39999	2	

Bangalore City the 1st October 1917

vement Trust Board

red by the City Improvement Trust Board,
ich fell due, and the Amount
up to end of 1916 17

Granted				Instalment of principal due up to end of 1916 17			Recoveries towards principal up to end of 1916 - 1917			Balance of principal for future recovery			Remarks
Total													
No	Amount												
7	8			9			10			11			12
86	6, 781	5	5	5,026	14	5	4 713	7	5	313	7	-	
27	2 231	6	-	1, 523	9	4	1, 190	8		333	1	4	
87	8, 431	5	3	4, 85 7	12	3	3, 901	2	2	956	10	1	
38	5, 894	15	9	3,416	14	5	2, 793	10	4	623	4	1	
116	5, 745	-	-	4, 604	6	-	4 331	11	-	272	11	-	
171	34, 926	2	-	10, 103	13	8	8, 935	15	8	1, 167	14	-	
50	11, 785	13	10	7, 231	-	-	6, 161	3	4	1, 069	12	8	
95	28, 290	-	-	12, 026	-	-	10, 660	4	7	4, 365	11	5	
21	7, 280	-	-	3 526	-	-	2 471	11	7	1, 054	4	5	
40	9, 656	14	2	6, 546	-		6, 611	9	6	234	6	6	
731	1, 21, 026	14	5	59 162	6	1	51 771	3	7	7 391	2	6	

[illegible] Chairman

Chairman

69

B. S. VI—G/321

[redacted]

No. of letter replied to

Section
File No
Serial No

REVENUE AND LAND REVENUE SECRETARIAT,
( )
, the 191

No 5313 Dt 23 3 18
Jud 11277-34 and Reminder
of 13

Date of issue 23 3 18

Signed by T Kesava Iyengar

To

The Superintendent,
Govt Press,
Bangalore

Sir,

I am directed to forward a copy of the Report with statements on the administration of the Mysore City Improvement Trust Bd for 1916-17 & to request that the usual no. of printed copies may be kept ready for issue along with the Govt Review

I have the honour to be
Sir
Your most obedient servant
for Secretary

over

23/3/18

,ist of enclosure

Copied by

Examined by

WD 69--GPB--60,000--12-1; 16

GRS VI-71]

SUBJECT Review the Administration Report for 1916-17 of the City Improvement Trust Bd, Mysore -

Diary No of letter replied to { 10 IX 1918 229 R

General and Revenue Secretariat

( )

, the 191

Date of issue

PUD 2

Signed by

this be

[Printed ?

treated as a standing order ?

published in the Gazette English part ?

translated ?

PUD 1+3

placed at the disposal of the press ?

published in the Gazette Kannada part ?

Section

File No 112-17

Serial No

Proceedings of the Government of His Highness the Maharaja of Mysore

Read -

Letter No: 327-554/C130&16-17 dy 25th Octr 1917 from the Chairman City Improvement Trust Board, Mysore submitting a report together with statements on the Administration of the Trust Board for the year 1916-17

2. Letter No 5540/Work D 1-338 and Work D 1-1220 dy 11/13 Octr 1917 and 15/16 March 1918 from the Comptroller Mysore Govt submitting the preliminary and final accounts of the Trust Board for 1916-17

~~Order Thereon — No.~~

OLC

order thereon.

1 Meetings. Ten meetings were held during the year of which 12 were ordinary and no adjourned. The average attendance at the meetings was 71 against 67 in the previous year.

2 Finances The total amount placed at the disposal of the Board during the year was Rs 4,50000 which was made up as follows:

Normal grant - Rs 3,50000

Additional grant - Rs 1,00000

Against this amount a sum of Rs 304365 was spent on works proper of the Board, Rs 73927 on acquisition and demolition of properties and Rs 39999 for advancing loans for housebuilding purposes, making a total of Rs 4,18,291; the remainder of the Expenditure, viz, Rs 31730 was on account of establishment, tools and plant etc which works out at 7%

List of enclosures.

Copied by

Examined by

G R S 27]

GENERAL AND REVENUE SECRETARIAT

(*Continuation sheet draft form.*)

12

on the total Expenditure and 10 4/7 on the amount Spent on works

The Comptroller's figure Showing a Sum of Rs 5,21,832 as the total receipts of the Board during the year is not correct as it Shows an Excess of Rs 71,832 over the sanctioned grants The attention of the Comptroller as well as the Chairman of the T.B. is invited in this Connection & the marginally noted Govt orders and to para 2 of the Govt views on the Annual Report of the Trust Board for the year 1913-14 Where it has been pointed out that the actual state grant should be so regulated as not to exceed the total sanctioned grants for the year Necessary action should be taken & have the necessary Corrections made in the accounts

Realisations by the Board, and opening balance

A Sum of Rs 41042 was realised by the Board by the sale proceeds of Silver

G.O. No 1062-B (Jud) 27-07-06 By 17th Jan 1908 (Class II)
G.O. No 221 (Jud) 27-01-14-03 By 12th July 1913 (Class II)

Class R

GPB—20,000—7-7 14

rods and other properties besides deductions from rents, profits, repayments and contributions A sum of Rs 50886 has been shown as a receipt under Reference heads by the Comptroller, and no reference to this amount has been made by the Chairman This requires an Explanation There is also a large difference in the opening balance between the accounts of the Comptroller and the Chairman which should be explained and steps taken to tally the accounts in both the offices

Work in Progress.

49 works are reported to have been under Construction of which 26 were new works and 23 incomplete works of the year previous The most important works in progress during the year and the outlay incurred thereon are shown in the following Statement A large outlay was as usual incurred on drainage works of these works the total outlay of Rs on outlay of about Rs 4,47,000 was incurred

No	Name of works	Sanc? Estimate	Outlay during the year	Total outlay
1	Laying sewer lines in no II, III (W&E), IV & V, Mylapore and Egmore areas	13,86,724	1,75,814	5,81,817
2	Laying out a sewage farm	30,560	6,330	21,104
3	Improvements to Davaneyamallat	1,28,600	30,442	40,604
4	Construction of Mundhiar bunding	1,43,800	5,031	5031
5	Laying out Chamiers Extension	1,12,348	30,342	31,213
6	Planting avenue trees	5,000	3,020	

114

Flag Q

on laying Sewer pipes in No II, III, Ittegad and Nazarbad drainage areas, the non-completion of which was noticed in last-year's review. These works were however started before sanction was obtained to the estimate. They should have been avoided.

Progress of acquisition

One hundred and Sixteen properties were acquired and demolished at a cost of Rs 73927 as against 194 properties at a cost of Rs 80432 in the previous year. Sanction was also accorded to the acquisition of 31 properties in the Fort in the order of their urgency at a total cost of Rs 167272 the expenditure to be incurred during 1916-17 & 17-18 having been limited to one lac. A sum of Rs 26790 was accordingly spent during the year under report on the acquisition of some of these properties. The question of Fort Improvements as a whole with a view to their speedy completion,

GPE—20,000—7-7 14

Engaging the consideration of Govt especially and orders will issue in due course.

Model houses

No new houses were constructed during the year and of the 7 houses that remained unsold at the end of the previous year 6 were sold and realised a sum of Rs 9588.

Building sites.

~~A sum of Rs 30085 was realised by the sale of building sites in various parts of the city~~

215 out of 1206 building sites in the several parts of the city were sold for Rs 30085. A large balance out of the amount is shown as having been held in deposit pending Execution of muttahalikas by the parties concerned. This is irregular and requires timely action should be taken as regards the obtaining of muttahalikas and the credit of the amount to the proper heads within a reasonable period. House building loans

loans

GENERAL AND REVENUE SECRETARIAT

(*Continuation sheet draft form*)

amounting to Rs 39,999 was issued to 141 persons as against Rs 23798 to 105 persons in the previous year. The demand for loans is increasing year after year as the result of the activities of the Board and the formation of new Extensions ~~arrangements are to be made~~ the proper manner to meet them. The question of the best manner of meeting the demand adequately is being considered by Govt and it is hoped that it will be possible to arrive at a satisfactory solution of the question at an early date.

The arrears amounting to Rs 7390 relating to the recovery of instalments due during the year are heavy and should receive the prompt attention of the Chairman with a view to their early reduction.

General

The report bears ample evidence to the increased activity of the Trust Board and though the prescribed programme has been departed from in several instances the improvement works are being pushed on vigorously. The rep

requests ~~made~~ Govt for additional grants
in recent years call for a thorough revision
of the programme of the Trust Board activities
A Comprehensive 5 year programme
submitted by the Chairman as required
in para 4 of the ~~last~~ previous years review is
receiving the attention of Govt; & that
steps may be taken & enable the Trust
Board & expedite the completion of the
more important and urgent improvement
works within a reasonable period. In conclusion,
Govt are pleased to record their appreciation of
good work done by the Trust Board
~~(good work done by the Chairman~~
, during the year under review
and the enthusiasm evinced
by the Members of the Board
and their labours which have

26/3 CBJ

25/3/18 Rev Sec'y

To The Chairman, City Improvement Trust Bd, Mysore
" Chief Engineer of Mysore
" Sanitary Commr in Mysore
" Comptroller, Mysore Govt
" Other Heads of Dept
" Presidents of the City Municipal Councils,
Bangalore & Mysore
The Press Tably.

78

Proceedings of the Government of
His Highness the Maharaja
of Mysore

Read.-

Letter No 327-S.54/C.130 of 16-17 dated 25th October 1917 from the Chairman City Improvement Trust Board, Mysore, - submitting a report, together with statements, on the administration of the Trust Board for the year 1916-17

2. Letters Nos. 5540 W A D 14365 and W A D 1-1220 dated 11th/13th October 17 and 15th/16th March 1918 from the Comptroller, Mysore Government, submitting the preliminary and final accounts of the - Trust Board for 1916-17.

Order No - 6490-540 fmd 1917-4

Dated, Bangalore the 4-6-18

1. M E E T I N G S. Thirteen meetings were held during the year of which, 12 were ordinary and one adjourned The average attendance at the meetings was 7 1 against 6.7 in the previous year.

2 F I N A N C E S. The total amount placed at the disposal of the Board during the year was Rs 4,50,000, which was made up as follows

NORMAL GRANT	Rs 3,50,000
ADDITIONAL GRANT..	Rs.1.00,000

Against this amount a sum of Rs 304365 was spent on works proper of the Board, Rs 73927, on acquisition and demolition of properties, and Rs. 39999, for advancing loans for house building purposes, making a total of Rs 4,18,291. The remaining expenditure viz Rs 31,730, was on account of establishment tools and plant, etc, which works out at 7% on the total expenditure and 10 4% on the amount spent on works. The Comptroller's figures showing a sum of Rs 5,21,832 as the total receipts of the Board during the year is not correct as it shows an excess of Rs 71,832 over the sanctioned grants. The attention of the Comptroller as well as the Chairman of the Trust Board is invited in this connection to the marginally noted Government Orders and to para 2 of the Government review on the Administration Report of the Trust Board for the year 1913-14 where it has been pointed out that the actual state grant should be so regulated as not to exceed the total sanctioned grants for the year Necessary action should be taken to have the corrections made in the accounts

G O No 6862-8, Ml 77-07-(1) dated 17th January 1908, read with G O No 221-5/51-14-63 dated 12th July 1915.

3 REALISATION BY THE BOARD

a OPENING BALANCE

A sum of Rs 41042 was realised by the Board by the sale proceeds of sites, lands and other properties, besides realisations from rents, profits repayments and contribution A sum of

Rs 50886/- has been shown as a receipt under suspense heads by the Comptroll and no reference to this amount has been made by the Chairman This requires explanation There is also a large difference in the opening balance between the accounts of the Comptroller and the Chairman, which should be explained and steps taken to tally the accounts in both the Offices

4 WORKS IN PROGRESS

49 works are reported to have been under construction of which 26 were new works and 23 incomplete works of the year previous The most important works in progress during the year and the outlay incurred thereon are shown in the following statement

Name of works	Sanctioned estimate	Outlay during the year	Total outlay.
1 Laying sewer pipes in No II, III (i) & (ii), IV & V Nazarbad drainage areas	1386724	175814	581817
2 Laying out a sewage farm	30560	6330	21104
3 Improvement of Devaraj Market.	123500	30462	40604
4. Construction of Municipal Office buildings	143800	5031	5031
5. Laying out Chamundi Extension	112348	30342	31213
6 Planting avenue trees	5000	3020	-

A large outlay was as usual incurred on drainage works Of the total expenditure of Rs 182744 incurred on these works an outlay of about Rs 147000 was incurred on laying sewage pipes in No II, III

8/

Ittigegud and Nazarbad drainage areas, ~~the non-completion of which was noticed in last year's review~~ These works were, however, started before sanction was obtained to the Estimates This should have been avoided.

6 PROGRESS OF ACQUISITION

One hundred and sixteen properties were acquired and demolished at a cost of Rs 73927 as against 194 properties at a cost of Rs 80432 in the previous year Sanction was also accorded to the acquisition of 31 properties in the Fort in the order of their urgency at a total cost of Rs 167572 the expenditure to be incurred during 1916-17 and 1917-18 having been limited to one lac A sum of Rs 26790 was accordingly spent during the year under report on the acquisition of some of these properties. The question of Fort Improvements as a whole with a view to their speedy completion is engaging the consideration of Government separately and orders will issue in due course

MODEL HOUSES

No new houses were constructed during the year and of the 7 houses that remained unsold at the end of the previous year, 6 were sold and realised a sum of Rs 9588

7 BUILDING SITES

215 out of 1286 building sites in the several parts of the City were sold for Rs 30085. A large balance out of this amount is shown as having been

held in deposit pending the execution of mutchalikas by the parties concerned. This is irregular and timely action should be taken as regards the obtaining of mutchalikas and the credit of the amount to the proper heads within a reasonable period.

HOUSE BUILDING LOANS.

Loans amounting to Rs 39,999 were issued to 141 persons as against Rs 23798 to 105 persons in the previous year. The demand for loans is increasing year after year as the result of the activities of the Board and the formation of new Extensions The question of the best manner of meeting this demand adequately is being considered by Government and it is hoped that it will be possible to arrive at a satisfactory solution at an early date

The arrears amounting to Rs 7390 relating to the recovery of instalments due during the year are heavy and should receive the prompt attention of the Chairman with a view to their early reduction

G E N E R A L

The report bears ample evidence to the increased activity of the Trust Board and though the prescribed programme has been departed from in several instances, the improvement works are being pushed on vigorously The repeated requests made to Government for additional grants in recent years call for a -

thorough revision of the programme of the Trust Board activities A comprehensive 5 year programme submitted by the Chairman as required in para 4 of the previous year's review is receiving the attention of Government, ~~so that steps may be taken~~ to enable the Trust Board to expedite the completion of the more important and urgent improvement works within a reasonable period

In conclusion, Government are pleased to record their appreciation of the good work done by the Trust Board during the year under review

Offg Secretary to Government,
Revenue Department.

To

The Chairman, City Improvement T Board
The Chief Engineer of Mysore
The Sanitary Commissioner in Mysore.
The Comptroller, Mysore Government.
The other Heads of Departments
The Presidents of the City Municipal Councils, Bangalore & Mysore

PRESS TABLE

SVS

Government of His Highness the Maharaja of Mysore.

GENERAL AND REVENUE DEPARTMENTS

G O. No. 6490-540—Ml. 112-17-4, dated 21st May 1918.

Administration Report

Review the —— of the Mysore City Improvement Trust Board for the year 1916-17

W D A2048-GPB—6-6 18—100

No 6490-540—ML 112-17-4, DATED 21ST MAY 1918

In conclusion, Government are pleased to record their appreciation of the good work done by the Chairman and the members of the Trust Board during the year under review

B RAMASWAMAIYA,
Secy. to Govt Rev Dept

To—The Chairman, City Improvement Trust Board Mysore
The Chief Engineer of Mysore
The Sanitary Commissioner in Mysore
The Comptroller, Mysore Government
The other Heads of Departments
The Presidents of the City Municipal Councils, Bangalore and Mysore
PRESS TABLE

Exd—C R.